

*TP*  
KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 24 1967  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Well Plugging Authority,  
issued, January 5, 1967

Operator's Full Name Bovaird Supply Company 15-185-12964-0000

Complete Address: P. O. Box 2590, Tulsa, Oklahoma

Lease Name Crissman Well No. # 5

Location NW SE SW Sec. 16 Twp. 23 Rge. 14 (E) (W) W

County Stafford Total Depth 4055'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Pipe Puller, Inc.

Address: Box 486, Ellinwood, Kansas License No. 462

Operation Completed: Hour 2:30PM Day 23rd Month Jan. Year 1967

The Above well was plugged as follows:

224' of 10 3/4" surface pipe, cemented with 225 sacks. 4054' of 7"  
long string, cemented with 200 sacks. Plug back T.D. 3850'. Top perferation  
3607'. Bottom of the hole was sanded to 3600', and cemented with 6 sacks,  
through the dump bailer. 2300' of 7" long string was recovered from the  
hole. Bridge plug was pushed in fluid to 220', bridge plug and rock bridge  
from 220' to 200'. 30 sacks of cement was pumped at 200', through 7 joints  
of 2" tubing. Hole was baile& down to 40', rock bridge from 40' to 30',  
and cemented with 15 sacks to the base of the cellar. This cementing was  
done by Pipe Pullers, Inc.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elvira  
Well Plugging Supervisor

DATE 1/24/67  
INV. NO. 4655-111