

R
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 9 1967
5-9-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Well Plugging Authority,
renewed April 20, 1967,
original issued Jan. 11, 1967

Operator's Full Name Bovaird Supply Company *15-185-129-63-0000*

Complete Address: P. O. Box 2590, Tulsa, Oklahoma 74101

Lease Name Crissman Well No. # 4

Location SE ^{NE} SW Sec. 16 Twp. 23 Rge. 14 (E) W

County Stafford Total Depth 4026'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Pipe Pullers, Inc.

Address: Box 486, Ellinwood, Kansas License No. 462

Operation Completed: Hour 11:45AM Day 8th Month May Year 1967

The Above well was plugged as follows:

220' of 10 3/4" surface pipe, cement circulated. 4025' of 7" long string,
cemented with 250 sacks. Plug back T.D. 3700'. Top perferation 3663'.
Bottom of the hole was sanded to 3650', and cemented with 6 sacks, through
the dump bailer. 2450' of 7" long string was recovered from the hole.
Bridge plug was pushed in fluid to 210', bridge plug and rock bridge from
210' to 200'. 25 sacks of cement was pumped on plug at 200', through 175'
of 2" tubing. Fluid in the hole was bailed down to 35', bridge plug and
rock bridge from 35' to 30', and cemented with 10 sacks to the base of the
cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Achie Elving
Well Plugging Supervisor

DATE 5/11/67
INV. NO. 5187-W