

<sup>14</sup>  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

FEB 10 1967

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Well Plugging Authority,  
issued January 11, 1967.

Operator's Full Name Bovaird Supply Company 15-185-00043-0000

Complete Address: P. O. Box 2590, Tulsa, Oklahoma

Lease Name Crissman Well No. # 1

Location NE NE SW Sec. 16 Twp. 23 Rge. 14 (E) (W) W

County Stafford Total Depth 4085'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Pipe Puller, Inc.

Address: Box 486, Ellinwood, Kansas License No. 462

Operation Completed: Hour 10:30AM Day 8th Month Feb. Year 1967

The Above well was plugged as follows:

212' of 8 5/8" surface pipe, cemented with 225 sacks. 4073' of 5 1/2" long  
string, cemented with 150 sacks. Plug back T.D. 3721'. Top perferation 3609'.  
Bottom of the hole was sanded to 3600', and cemented with 5 sacks, through  
the dump bailer. 2008' of 5 1/2" long string was recovered from the hole. Bridge  
plug was pushed in fluid to 190', bridge plug and rock bridge from 190' to 180'  
7 joints of 2" tubing, totaling 175' was run in the surface pipe. 25 sacks of  
cement was pumped through the 2" tubing at 175'. Fluid in the hole was bailed  
down to 40', bridge plug and rock bridge from 40' to 30', and cemented with 10  
sacks to the base of the cellar. This cement was pumped by Pipe Pullers, Inc.  
I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving  
Well Plugging Supervisor

DATE 2/10/67  
INV. NO. 4744-11