

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

FEB 8 1967

CONSERVATION DIVISION
Wichita, Kansas

2-2-67

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Well Plugging Authority,
issued January 11, 1967

Operator's Full Name Bovaird Supply Company 15-185-00016-00-01

Complete Address: P. O. Box 2590, Tulsa, Oklahoma

Lease Name Beaver Well No. # 1

Location SE SE NW Sec. 16 Twp. 23 Rge. 14 (E) (W) W

County Stafford Total Depth 4043'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Pipe Pullers, Inc.

Address: Box 486, Ellinwood, Kansas License No. 462

Operation Completed: Hour 3:35 PM Day 2nd Month Feb. Year 1967

The Above well was plugged as follows:

201' of 10 3/4" surface pipe, cemented with 200 sacks. 4039' of 7" long
string, cemented with 100 sacks. Plug back T.D. 3686'. Top perferation
3655'. Bottom of the hole was sanded to 3625', and cemented with 6 sacks.
3017' of 7" long string was recovered from the hole. Bottom of the surface
pipe was tagged at 175'. bridge plug and rock bridge from 175' to 165' was
set in fluid. 35 sacks of cement was pumped in fluid, through 6 joints of
2" tubing totaling 162' on top of bridge at 165'. Fluid in the hole was bailed
down to 40', rock bridge from 40' to 30', and cemented with 10 sacks to the
base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 2/3/67
INV. NO. 4706-W

Signed: Archie Elving
Well Plugging Supervisor