

KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 29 1966

CONSERVATION DIVISION
Wichita, Kansas

15-185-0005-0000

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Aspen Drilling Company

Complete Address: P. O. Box 783, Great Bend, Kansas

Lease Name Crissman Well No. # 2

Location SW NE SW Sec. 16 Twp. 23 Rge. 14 (E) (W) W

County Stafford Total Depth 4060'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Forbes Casing Pulling, Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 1:15 AM Day 28th Month July Year 1966

The Above well was plugged as follows:

214' of 10 3/4" surface pipe, cemented with 200 sacks. 4059' of 7" long string
cemented with 125 sacks. 3973' of 5 1/2" long string, cemented with 60 sacks.
Plug back T.D. 3634'. Top perforation 3615'. All perforations were squeezed
with 15 sacks. 1450' of 7" long string was recovered from the hole. 1450' of
5 1/2" long string was recovered from the hole. Bridge plug was pushed in fluid
to 210', rock bridge from 210' to 200'. 16 sacks of cement was mixed in a
barrel, and put on plug at 200', and let set for days. Hole was bailed dry
and 22 sacks of cement was added to the plug. Hole was filled with mud to 40'
rock bridge from 40' to 30', and cemented with 15 sacks to the base of the
cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 7/29/66
INV. NO. 3654-W