

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Intent to Drill,
filed march 7, 1967.

RECEIVED
STATE CORPORATION COMMISSION

MAR 20 1967

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name J. M. Stewart 15-185-20017-0000

Complete Address: 608 Union Center Bldg., Wichita, Kansas

Lease Name Cornwell Well No. # 1

Location SE NE SE Sec. 17 Twp. 23 Rge. 14 (E) (W) W

County Stafford Total Depth 3929'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Hellar Drilling Company, Inc.

Address: 1014 Union Center Bldg., Wichita, Kansas License No. _____

Operation Completed: Hour 12:45PM Day 18th Month March Year 1967

The Above well was plugged as follows:

250' of 8 5/8" surface pipe, cement circulated with 220 sacks. Hole had
been making water and a squeeze job was necessary. Heavy drilling mud
was pumped into the surface pipe, through an 8 5/8" swage, and 75 sacks
of cement was pumped through the 8 5/8" swage to a pressure of 400 lbs.
A wiping plug was run between the mud and the cement.
This cementing was done by Halliburton Cementing Company.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 3/20/67

INV. NO. 4928-W

Signed: Audie Elving
Well Plugging Supervisor