

Yp
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

15-185-30059-0000

RECEIVED
STATE CORPORATION COMMISSION

JUN 1 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Rupe-Stoskopf, c/o Gabbert-Jones, Inc.

Complete Address: 514 Orpheum Bldg., Wichita, Kansas

Lease Name Redetzke Well No. # 1

Location SW SW SE Sec. 18 Twp. 23 Rge. 14 (E) (W) W

County Stafford Total Depth 4090'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Gabbert-Jones, Inc.

Address: 514 Orpheum Bldg., Wichita, Kansas License No. _____

Operation Completed: Hour 9:00 PM Day 28th Month May Year 1965

The Above well was plugged as follows:

270' of 8 5/8" surface pipe, cement circulated with 275 sacks. Fluid
level in the hole was at 125'. 1st cementing plug and 1/2 sack of hulls
was pushed in fluid to 265', and cemented with 25 sacks, through the
drill pipe. Hole was filled with drilling mud to 40', 2nd cementing
plug, bridged solid with hulls on fluid at 40', and cemented with 10
sacks to the base of the cellar. Rat hole bridged and cemented with
2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 6/2/65

INV. NO. 1245-11