

SIDE ONE

(Rules 82-3-130 and 82-3-107)

This form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ninety (90) days after the completion of a well, regardless of how the well was completed.

FOR INFORMATION REGARDING THE NUMBER OF COPIES TO BE FILED AND APPLICATIONS REQUIRING COPIES OF ACO-1 FORMS SEE PAGE TWO (2), SIDE TWO (2) OF THIS FORM.

Letter requesting confidentiality attached.

Attach ONE COPY of EACH wireline log run (i.e. electrical log, sonic log, gamma ray neutron log etc.)***Check here if NO logs were run _____.

PLEASE FILL IN ALL INFORMATION. IF NOT AVAILABLE, INDICATE. IF INFORMATION LATER BECOMES AVAILABLE, SUBMIT BY LETTER.

LICENSE # 7930 EXPIRATION DATE June 30, 1984

OPERATOR Merit Energy Corporation API NO. 15-145-21,043-0000

ADDRESS 717 17th Street - Suite 1750 COUNTY Pawnee

Denver, Colorado 80202 FIELD Antone

** CONTACT PERSON David W. Bieber PROD. FORMATION Lansing

PHONE 303/293-9169

PURCHASER Clear Creek, Inc. LEASE Fleske

ADDRESS P. O. Box 1045 WELL NO. 1-10

McPherson, Kansas 67460 WELL LOCATION SW SE NE

DRILLING Mustang Drilling & Exploration, Inc. 2302 Ft. from North Line and

CONTRACTOR P.O. Box 1609 990 Ft. from East Line of:

ADDRESS Great Bend, Kansas 67530 the NE (Qtr.) SEC 10 TWP 21s RGE 18W (W).

PLUGGING -- WELL PLAT. (Office Use Only)

CONTRACTOR _____

ADDRESS _____

		NE/4	
		IP	
		0	

KCC
KGS
SWD/REP _____
PLG. _____
NGPA _____

TOTAL DEPTH 4056' PBTD _____

SPUD DATE 6-23-83 DATE COMPLETED 8-13-83

ELEV: GR 2084 DF 2093 KB 2095

DRILLED WITH (CMBKE) (ROTARY) (AMR) TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING

USED TO DISPOSE OF WATER FROM THIS LEASE N/A

Amount of surface pipe set and cemented 1004' DV Tool Used? No

TYPE OF COMPLETION THIS AFFIDAVIT APPLIES TO: (Circle ONE) - Oil Shut-in Gas, Gas, Dry, Disposal, Injection, Temporarily Abandoned. If OWWO, indicate type of re-completion _____ Other completion _____ NGPA filing _____

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

A F F I D A V I T

George M. Schneider, being of lawful age, hereby certifies that:

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.

George M. Schneider
(Name)

SUBSCRIBED AND SWORN TO BEFORE ME this 16th day of November, 1983.

Orlith Davis
(NOTARY PUBLIC)

MY COMMISSION EXPIRES: My commission expires Dec. 16, 1984

RECEIVED
KANSAS CORPORATION COMMISSION
11-18-83

** The person who can be reached by phone regarding any questions concerning this information.

NOV 18 1983
CONSULTING
Wichita, Kansas

PAGE TWO (Side One)

ACO-1 WELL HISTORY

OPERATOR Merit Energy Corporation LEASE NAME Fleske

SEC. 10 TWP. 21S RGE. 18

(E)
(W)

FILL IN WELL LOG AS REQUIRED: WELL NO.

Show all important zones of porosity and contents thereof; corad intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Anhydrite & Shale	1149	1177	Stone Corral	+946
Dolomite V.S.S.G.	2100	2109	Herrington	-5
Limestone V.S.S.G.	2150	2167	Winfield	-55
Black Shale	3494	3500	Heebner	-1399
Oolitic Ls. S.S.O.	3585	3600	Lansing "A"	-1490
DST#1 15-30-40-120 ISIP 1272 FSIP 1276 IFP 61-74 FFP 81-105 IHMP 1938 FHMP 1936 Rec. 165' muddy water BHT 104 deg. F	3576	3596	Lansing "A"	
Oolitic Ls. S.S.O.	3763	3786	Lansing "J"	-1668
DST#2 Mis-Run	3771	3779	Lansing "J"	
DST#3 15-30-40-120 ISIP 1384 FSIP 1405 IFP 127-140 FFP 149-158 IHMP 2045 FHMP 2051 Rec. 130' OCM (20% oil) BHT 110 deg. F	3756	3779	Lansing "J"	
Black Shale	N/A	3854	Base Kansas City	-1759
Shaley Sd V.S.S.O.	3984	3989	Cherokee Sd.	-1889
DST#4 16-30-46-115 ISIP 764 FSIP 1057 IFP 82-82 FFP 84-92 IHMP 2118 FHMP 2016 Rec. 13' VSO&GCM (5% oil) BHT 112 deg. F	3973	3981	Cherokee Sd.	
Shaley Sand	4004	4018	Conglomerate	-1909
Dolomite	4018	TD	Arbuckle	-1923

RELEASED
 SEP 12 1984
 FROM CONFIDENTIAL

RELEASED
 Date: SEP 1 1984
 FROM CONFIDENTIAL