

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Pawnee County, Sec. 2 Twp. 21S Rge. (E) 19 (W)

Location as "NE/CNW&SW" or footage from lines SE NE SW  
Lease Owner Ideker  
Lease Name Ideker "A" Well No. 1  
Office Address 205 Central Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed Feb. 14 1964  
Application for plugging filed Feb. 14 1964  
Application for plugging approved Feb. 14 19 64  
Plugging commenced Feb. 14 19 64  
Plugging completed Feb. 14 19 64  
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation Depth to top Bottom Total Depth of Well 1310 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	205'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set plug at 550' with 35 sacks cement, plug at 200' with 1/2 sack hulls & 35 sacks cement, plug at 40' with 1/2 sack hulls & 10 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION

MAR 5 1964

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Jones-Gebert Oil, Inc.  
Address 205 Central Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

George R. Jones (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
205 Central Building, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 4th day of March, 1964

My commission expires January 8, 1968

[Signature]  
Lois J. McCoy Notary Public.

DRILLER'S LOG

Company: Jones-Gebert Oil, Inc.  
 Contractor: Jones-Gebert Oil, Inc.  
 Farm: Ideker "A" #1, SE NE SW  
 Section 2-21S-19W  
 Pawnee County, Kansas  
 Commenced: 2/1/64  
 Completed: 2/14/64  
 Casing: 205' of 8-5/8" with 175 sacks

0	-	160	Surface Soil & Sand
160	-	207	Clay & Shale
207	-	680	Shale & Red Bed
680	-	830	Dakota Sand
830	-	1260	Shale & Shells
1260	-	1287	Anhydrite
1287	-	1310	Shale & Shells
		1310	Rotary Total Depth


I, George R. Jones, do hereby certify that the above and foregoing is a true and correct copy of the log of the #1 Ideker "A", SE NE SW, Section 2-21S-19W, Pawnee County, Kansas, as reflected by the files of Jones-Gebert Oil, Inc.

  
 GEORGE R. JONES

State of Kansas, County of Sedgwick ) ss:

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 4th day of March, 1964.

My Commission Expires:  
 January 8, 1968

  
 Lois J. McCoy, Notary Public

RECEIVED  
 STATE CORPORATION COMMISSION  
 MAR 5 1964  
 CONSERVATION DIVISION  
 Wichita, Kansas