




STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Pawnee County, Sec. 2 Twp. 21 Rge. 19 (E) (W) X  
Location as "NE/CNW/SW" or footage from lines. NW SW SE  
Lease Owner Mull Drilling Company  
Lease Name Ideker Well No. 1  
Office Address P. O. Box 349 Russell, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed 9-3-69 19\_\_\_\_  
Application for plugging approved 9-4-69 19\_\_\_\_  
Plugging commenced 10-4-69 19\_\_\_\_  
Plugging completed 10-15-69 19\_\_\_\_  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4283 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	408	None
				4 1/2	None	2343

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 21 1969

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set up pole. Sanded bottom back to 4200'. Started to rig up unit.

Finished rigging up. Had water pumped out of cellar. Took off braden head and put on control head. Welder cut off braden head. Working pipe - 23" stretch at 16 joints.

Shot pipe at 3685'. Worked pipe - no change in stretch. Allied Cementing Company spotted 80 bbls. of oil. Central Transport pumped plug to 3600' with salt water 800# to 1,000# pressure.

Worked pipe - no change in stretch. Working pipe - 25" stretch at 16 joints. Put up breakout.

Shot pipe at 3200' - 3005' - 2495' and 2370'. Pulled 25 joints of pipe.

Finished pulling pipe. Took off control head - put on plug container. Central Transport pumped out cellar. Talled pipe. Allied Cementing Company squeezed well with 20 sacks of gel and 120 sacks of 6% pozmix cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling Company, Inc.  
Address P. O. Box 221 Great Bend, Kansas 67530

STATE OF Kansas, COUNTY OF Barton, ss.  
James W. Rockhold (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold  
P. O. Box 221 Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 17 day of October, 1969

My commission expires May 27, 1973

Notary Public.

ROTARY DRILLING LOG

Operator: Mull Drilling Company  
#1 Ideker  
150° South NW SW SE  
Section 2-21S-19W  
Pawnee County, Kansas

Contractor: Rains & Williamson Oil Co.  
Commenced: 6-11-66  
Rotary Released: 6-24-66  
Remarks: Set 409° of 8-5/8" surface  
pipe with 225 sacks of GL3.

Cemented 4-1/2 pipe 1' off  
bottom with 150 sacks of  
60-40 posmix cement.

FORMATIONS

Soil and Clay	40°
Shale	253°
Sand	284°
Shale	680°
Sand	815°
Shale	1050°
Shale & Red Bad	1262°
Anhydrite	1287°
Shale	1435°
Shale & Shells	1980°
Shale	2105°
Lime & Shale	2430°
Lime	2715°
Shale	2839°
Lime & Shale	3045°
Shale w/Lime	3215°
Shale	3390°
Shale & Lime	3530°
Lime & Shale	4018°
Lime	4055°
Lime & Shale	4213°
Sand	4229°
Lime	4283°
Total Depth	4283°

*Top of cement 3780*

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 4 1966  
CONSERVATION DIVISION  
Wichita, Kansas

We certify the above log is true and  
correct to the best of our knowledge  
and belief.

RAINS & WILLIAMSON OIL CO.

*Wilson Rains*  
Wilson Rains, Partner

Subscribed and sworn to before me, a Notary Public in and for the State of  
Kansas, County of Sedgwick, this 27th day of June, 1966.

My Commission Expires: 3-3-70

*Mary J. Brown*  
Mary J. Brown Notary Public