


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Flat

Pawnee County. Sec. 5 Twp. 21S Rge. 19 (E) (W)
Location as "NE/CNW/SE/SW" or footage from lines SE NE NE
Lease Owner Sunray DX Oil Company
Lease Name A. Lotas Well No. 1
Office Address Ellinwood, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 4-27-65 _____ 19____
Plugging completed 4-30-65 _____ 19____
Reason for abandonment of well or producing formation _____
Dry
If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well PB 4385 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	388	None
				5 1/2	None	2514

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Cleaned out cellar. Sanded to 4300'. Dumped 8 sacks of cement. Working pipe.
Shot pipe at 3220'. Pulled 125,000 tension. Working pipe. Mud came in at 2220'.
Circulating mud. Shot pipe at 3000' - 2800' - 2700' - 2600' & 2510'. Pulling pipe.
Pulling pipe. Plugging well. Circulated mud at 600' with 32 sacks of cement. Dumped 20 sacks of cement at 540'. Dumped 30 sacks of mud at 240'. Capped well with 10 sacks.

RECEIVED
STATE CORPORATION COMMISSION
MAY 10 1965
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Forbes Casing Pulling, Inc.
Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes
P. O. Box 221 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 7 day of May 19 65

My commission expires May 27, 1965
Notary Public.

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


COPY

Company: SUNRAY DX OIL CO.
Farm: Latas No. 1

SEC. 5 T. 21 R. 19W
C SW NE

Total Depth. 4420'
Com. 3-7-65 Comp. 3-20-65
Shot or Treated.
Contractor. Murfin Drlg. Co.
Issued. 8-28-65

County Pawnee
KANSAS



Elevation. 2194' KB

Production. Temp Abd.

8 5/8" 338' w/257 sx cem.
5 1/2" 4437.12' w/175 sx cem.

Figures Indicate Bottom of Formations.

shale, red bed	760
sand	915
red bed	1335
anhhdrite	1361
shale, red bed	1860
lime, shale	3700
lime	4265
Cherokee shale	4285
Cherokee shale, Mississippi	
chert	4320
lime	4393
Kinderhook shale	4420
Total Depth	

TOPS: SCOUT

* Anhhhdrite	1335
Heebner	3701
Lansing	3761
B/Kansas City	4089
Cherokee shale	4216
* Cherokee sand	4240
Mississippi	4312
* Gilmore City	4371
Kinderhook	4390

RECEIVED
STATE CORPORATION COMMISSION

FEB 22 1966

Wichita, Kansas