

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Pawnee County, Sec. 12 Twp. 21S Rge. 19W (E) (W) X

Location as "NE/CNW/SW" or footage from lines 150' E of C SE SW  
Lease Owner Clinton Oil Co.  
Lease Name Wm. Pieschl Well No. 1-V  
Office Address 217 North Water, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) D&A  
Date well completed June 17 1971  
Application for plugging filed June 17 1971  
Application for plugging approved June 17 1971  
Plugging commenced June 17 1971  
Plugging completed June 17 1971  
Reason for abandonment of well or producing formation D&A



If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4300 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	444'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plug @ 600' w/50 sx  
Plug @ 400' w/25 sx  
Plug @ 40' w/10 sx, 1/2 sx hulls

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 23 1971  
CONSERVATION DIVISION  
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Red Tiger Drilling Company  
Address 1720 Wichita Plaza, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Jim Farrice (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jim Farrice  
1720 Wichita Plaza, Wichita, Kansas  
(Address)

Subscribed and sworn to before me this 21st day of June, 1971  
Virginia H. Albert  
Notary Public.  
My commission expires July 23, 1974



DRILLERS LOG

Pieschl 1-V

CASING RECORD:	COMPANY:	Clinton Oil Company	DESCRIPTION:
8 5/8" @ 451' w/250 sx cement	CONTRACTOR:	Red Tiger Drilling Co.	150' E of C SE SW 12-21S-19W Pawnee County, Kansas
TOTAL DEPTH: 4300'	COMMENCED:	June 6, 1971	ELEVATION:
	COMPLETED:	June 17, 1971	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay	0	40	
Clay, Sand, Shale	40	345	
Shale	345	451	
Shale & Red Bed	451	650	
Sand	650	800	
Shale & Red Bed	800	1231	
Anhydrite	1231	1256	
Shale	1256	1405	
Shale & Lime	1405	3710	
Lime	3710	4225	
Lime, Sand, Chert	4225	4300	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Jim Farrice  
Jim Farrice

Subscribed and sworn to before me this 21st day of June, 1971.



Virginia K. Albert  
Notary Public

My Commission Expires:

July 23, 1974

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 23 1971  
CONSERVATION DIVISION  
Wichita, Kansas