


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Pawnee County, Sec. 11 Twp. 21 Rge. 19 (E) (W) X
Location as "NE/CNW/SW" or footage from lines NW NW NE
Lease Owner Mull Drilling Company, Inc.
Lease Name Mezger Well No. 1
Office Address 1625 Wichita Plaza Building
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 1-19-67 19
Application for plugging approved 1-20-67 19
Plugging commenced 1-23-67 19
Plugging completed 2-4-67 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey
Producing formation Depth to top Bottom Total Depth of Well FB 4214 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	248	None
				4 1/2	None	3615

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Moved in. Rigged up. Dug cellar. Unpacked braden head. Working pipe - had 15" tension at 18 joints.

Sanded back from 4214' to 4120'. Dumped 4 sacks of cement on bridge.

Spotted 120 bbls of oil. Pumped plug to 3515'. Pumped bridge out from 2937' to 3611'.

Working pipe. Pulling pipe.

Pulling pipe. Cleaned and doped collar threads.

Plugging well. Mixed 20 sacks of mud and 85 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.
Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes
P. O. Box 221 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 7 day of February 1967

My commission expires May 27, 1969

Notary Public.

ROTARY DRILLING LOG

Operator: Mull Drilling Company, Inc. Contractor: Rains & Williamson Oil Co.
 #1 Mezger Commenced: 8-7-66
 NW NW NE Sec. 11-21S-19W Rotary Released: 8-18-66
 Pawnee County, Kansas Remarks: Set 248.40' of 8-5/8"
 surface pipe with 170
 sacks GL3.

Set 4-1/2" casing 1' off
 bottom, cemented with
 150 sacks 60-40 pozmix.

FORMATIONS

Soil Clay, Shells	70'
Shale	180'
Sand	205'
Shale	678'
Sand	825'
Shale	1015'
Shale & Red Bed	1263'
Anhydrite	1310'
Shale	2060'
Lime & Shale	2335'
Lime	2655'
Lime & Shale	2795'
Shale & Lime	3205'
Shale	3330'
Shale & Lime	3640'
Shale w/Lime Stks.	3800'
Lime	4289'
Rotary Total Depth	4289'

RECEIVED
 STATE CORPORATION COMMISSION

JAN 24 1967

CONSERVATION DIVISION
 Topeka, Kansas

We certify the above log is true and
 correct to the best of our knowledge
 and belief.

RAINS & WILLIAMSON OIL CO.

Wilson Rains
 Wilson Rains, Partner

Subscribed and sworn to before me, a Notary Public in and for the State of
 Kansas, County of Sedgwick, this 22nd day of August, 1966.

My Commission Expires:
 3-3-70

Mary J. Brown
 Mary J. Brown Notary Public