

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Pawnee

County. Sec. 10 Twp. 21S Rge. 19 XXXX (W)

Location as "NE/CNW&SW&" or footage from lines SE SE NW

Lease Owner D. R. Lauck Oil Co. Inc. & Sunray Mid-Continent

Lease Name Fallt Well No. 1

Office Address 301 So. Broadway Wichita Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed December 31 19 58

Application for plugging filed " 31 19 58

Application for plugging approved " 31 19 58

Plugging commenced " 31 19 58

Plugging completed " 31 19 58

Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Frank Braadfoot

Producing formation Depth to top Bottom Total Depth of Well 4397 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	350	8 5/8"	350'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole filled with mud 4397 - 300
 plug 300 - 296
 cement 296 - 35
 plug 35 - 31
 cement 31 - 6 bottom of cellar

STATE OF KANSAS
 CONSERVATION DIVISION
 JAN 9 1959
 WICHITA, KANSAS

1-9-59

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sun Cementing Co.

Address Great Bend Kansas

STATE OF Kansas COUNTY OF Sedgwick ss.

John H. Knightley (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct So help me God.

(Signature) John H. Knightley
Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 8 day of January, 19 59

ELIZABETH GAY
 Notary Public
 My commission expires Sept. 14, 1959

Elizabeth Gay
Notary Public.

10 21 1959
 BOOK PAGE 9 44

D. R. Lauck Oil Company, Inc.
& Sunray Mid-Continent Oil Company

Fallt #1

SE SE NW Sec.10-21S-19W
Pawnee County, Kansas

Commenced: December 17, 1958
Completed: December 31, 1958

Casing Record: 350' 8 5/8"

cemented with 220 sacks
Calcium Chloride 400#s

Elevation: GR 2175; DF 2178; KB 2180;

Drillers Log

Tops

Welex

Clay	75	Anhydrite(Drillers)	1318+862	
shale	210	Heebner	3715-1535	3716-1536
sand & shale	270	Toronto	3733-1553	3736-1556
shale	280	Lansing	3770-1590	3770-1590
shale & clay	350	Base Kansas City	4093-1913	4092-1912
shale	365	Cherty Conglom.	4278-2098	4278-2098
shale & red bed	600	Mississippian	4338-2158	4338-2158
chalk & shale	620	Kinderhook sand	4394-2214	4394-2214
shale & red bed	750	Rotary Total Depth	4397-2217	4396-2216
sand	890			
red bed	1060	DST #1 (SS)	4240-4350; open 1 hr;	
red bed & shells	1318		strong blow 1 hr.	
Anhydrite	1345		recovered 520' muddy sa	
shale & shells & red bed	1485		salt water;	
shale & red bed	1600		IFP 90#, FFP 270#;	
shale & shells	1940		BHP 1065#;	
shale, red bed & lime	2140		shut in 30 min.	
lime & shale	2585			
shale & lime shells	2610			
shale & lime	2915	D & A		
lime & shale	3520			
lime	3673			
lime & shale	3710			
lime	3715			
Heebner	3720			
Lime & shale	3770			
Lime	4120			
shale & lime	4285			
shale, lime & sand	4305			
shale, Lime & chert	4338			
chert	4397 R.T.D.			

RECEIVED
STATE CORPORATIONS COMMISSION
JAN 9 1959
CONSERVATION DIVISION
Topeka, Kansas

PLUGGING			
FILE	SEC	10 T 21 R 19W	
BOOK	PAGE	9	LINE 44