


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Pawnee County. Sec. 10 Twp. 21 Rge. 19 (X) (W)
Location as "NE/CNW/SW" or footage from lines SE SE SE
Lease Owner L. C. Smitherman & Aurora Gasoline Co.
Lease Name Leadley Well No. 1
Office Address Box 627, Augusta, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed July 27 19 57
Application for plugging filed July 27 19 57
Application for plugging approved July 27 19 57
Plugging commenced July 27 19 57
Plugging completed July 28 19 57
Reason for abandonment of well or producing formation Dry

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well M.A. Rives
Producing formation Arbuckle Depth to top 4493 Bottom 4515 Total Depth of Well 4515 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Hebner	SW	3652	3670	0	0	0
Toronto	SW	3670	3708	0	0	0
Lansing	SW	3708	4028	0	0	0
Kansas City	SW	4028	4180	0	0	0
Cherokee	SW ³⁰	4180	4202	0	0	0
Conglomerate	SW	4202	4272	0	0	0
Mississippi	SW	4272	4320	0	0	0
Kinderhook Sand	SW	4320	4350	0	0	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set bottom plug at 440' with 20 sacks cement. Mud from 350' to 25'. Top plug with 5 sacks cement. Weld steel plate on top of surface casing.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor L. C. Smitherman Drilling Company
Address Box 627, Augusta, Kansas

STATE OF Kansas, COUNTY OF Butler, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Box 627, Augusta, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of August, 19 57

My commission expires January 28, 1961
Shirley Ann Jackson Notary Public
STATE CORPORATION COMMISSION

PLUGGING
FILE SEC. 10 T. 21 R. 19
BOOK PAGE 31 LINE 42

AUG 15 1957
CONSERVATION DIVISION
Wichita, Kansas
8-15-57

LEADLEY #1

Company: Aurora Gasoline Company
 Contractor: L. C. Smitherman Drilling Co.
 Commenced: July 9, 1957
 Completed: July 27, 1957
 Total Depth: 4515*

Location: SE SE SE, Section
 10-21S-19W, Pawnee County,
 Kansas
 Elevation: 2122 GL
 2127 Kelly Bushing
 Casing: 450* - 8 5/8"
 Cemented W/300 Sks.

Figures Indicate Bottoms of Formations:

Depth	Formation	
0	40	Soil & Clay
40	165	Shale & Lime Streaks
165	420	Lime & Shale
420	450	Lime
450	818	Shale Redbed
818	940	Dakota Sand
940	1270	Redbed
1265	1295	Anhydrite
1295	1340	Shells
1340	1535	Salt, Redbed, Shale
1535	1647	Shale, Lime Shells
1647	2125	Lime & Shale
2125	2205	Lime
2205	3020	Shale, Lime
3020	3050	Sand, Sandy Shale
3050	3095	Shale
3095	3510	Lime & Shale
3510	3553	Lime
3553	3760	Lime, Shale
3760	3855	Lime
3855	3898	Lime, Shale
3898	4051	Lime
4051	4115	Lime, Limy Shale
4115	4199	Lime
4199	4235	Lime & Shale
4235	4272	Conglomerate
4272	4316	Mississippi Chat
4316	4322	Mississippi Chat & Lime
4322	4335	Kinderhook
4335	4345	Lime & Shale
4345	4385	Chert & Lime
4385	4410	Cherty Lime
4410	4447	Lime
4447	4467	Lime & Dolomite
4467	4500	Lime
4500	4515	Lime & Chert
4515		Total Depth

We hereby certify the above and foregoing to be a true and correct copy of the Log on the Leadley #1, located in the SE SE SE, Section 10-21S-19W, Pawnee County, Kansas.

L. C. SMITHERMAN DRILLING COMPANY

Carl J. Lehr
 Carl J. Lehr

Subscribed and sworn to before me this 8th day of August, 1957.

Shirley Ann Jackson
 (Notary Public)

My commission expires January 28, 1961.

PLUGGING

FILE SEC 10 T 21 R 19 W
 BOOK PAGE 31 LINE 42

RECEIVED
 STATE CORPORATION COMMISSION

AUG 15 1957

DIVISION
 KANSAS