


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Pawnee County, Sec. 15 Twp. 21 Rge. 9 (X) (W)
Location as "NE/CNW/SW" or footage from lines NW NW NW
Lease Owner Aylward Drilling Company et al
Lease Name Weiden Well No. 1
Office Address 813 1st Nat'l Bank Bldg. Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 5 19 55
Application for plugging filed April 5 19 55
Application for plugging approved April 5 19 55
Plugging commenced April 5 19 55
Plugging completed April 5 19 55
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives, Pratt, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	1020	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled from 4530 to 300' with heavy mud; set Halliburton plug,
1/2 sack hulls and 20 sacks cement; heavy mud from 250' to 35';
1/2 sack hulls and 10 sacks cement from 35' to bottom of cellar

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Aylward Drilling Company
Address 813 1st Nat'l Bank Bldg. Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Paul W. Hesse (employee of owner) or ~~(Notary Public)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) Paul W. Hesse
813 1st Nat'l. Bank Bldg. Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 11TH day of April, 19 55

My commission expires December 11, 1957

Duane Jessup
Notary Public.

RECEIVED
STATE CORPORATION COMMISSION
APR 12 1955
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILED 215-121-19W
BOOK PAGE 129 PAGE 29

Casing Record:

WEIDEN #1

8-5/8" 1020'

Company: Aylward Drilling Company & Carter Oil Company
 Contractor: Aylward Drilling Company

Commenced: March 17, 1955
 Completed: April 5, 1955

Location:
 NW NW NW
 Sec. 15-21-19
 Pawnee County, Kansas

Elevation:
 2118 D.F.

	<u>From</u>	<u>To</u>	<u>Remarks</u>
Clay & Shells	0	70	D.S.T. #1 - 3594-3647
Sand & Shale	70	315	Open 20 min; Rec. 190' M.S.W.
Shale	315	420	BHP 1250#.
Shale & Sand	420	685	
Sand	685	905	D. S. T. #2 - 4220-4233
Sand & Shale & Red Rock	905	1015	Open 30"; Recovered 2310' S.W.
Shale	1015	1020	B.H.P. 1340#
Redrock	1020	1255	
Anhydrite	1255	1280	D.S.T. #3 - 4238-4255
Shale	1280	1335	Open 25"; Recovered 1690' S.W
Shale	1335	1570	BHP 1320#
Shale & Shells	1570	1875	
Shale	1875	2080	D.S.T. #4 - 4319-4340
Lime	2080	2110	Open 10" Recovered 600' S.W.
Lime	2110	2255	BHP 1275#
Lime	2255	2370	
Lime	2370	2435	D.S.T. #5 - 4267-4275
Lime	2435	2555	Open 60"; Rec. 810' S.W.
Lime & Shale	2555	2615	B.H.P. 1300#
Shale & Lime	2615	2745	
Lime	2745	2825	
Shale & Lime	2825	2970	<u>TOPS</u>
Lime & Shale	2970	3105	Heebner 3656
Lime & Shale	3105	3208	L. K.C. 3738
Lime & Shale	3208	3325	B. K.C. 4058
Lime	3325	3410	Cherokee 4177
Lime	3410	3495	Mississippi 4260
Lime	3495	3536	Khk. Shale 4320
Lime & Shale	3536	3735	Viola 4333
Lime	3735	3795	Simpson 4462
Shale & Lime	3795	3856	Arbuckle 4476
Lime	3856	3890	R.T.D. 4524 (Elec. Log)
Lime	3890	4177	
Conglomerate	4177	4233	
Lime & Shale	4233	4255	
Lime Shale & Chert	4255	4284	
Lime & Chat	4284	4328	
Lime Shale Chert	4328	4333	
Lime & Shale	4333	4359	
Lime Shale & Chert	4359	4386	
Lime & Shale	4386	4530 R.T.D.	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

Paul W. Hesse
 Paul W. Hesse

Subscribed and sworn to before me this 11TH day of APRIL, 1955.

NOTARY COMMISSION
 APR 12 1955

Duane Jessup
 Notary Public

My Commission Expires: December 11, 1957
 PAVANATION DIVISION
 Wichita, Kansas

PLUGGING
 FILE SEC 15 T-21-19W
 BOOK PAGE 109 LINE 29