


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Pawnee County, Sec. 32 Twp. 21S Rge. 19W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
C NW/4

Lease Owner Benson Mineral Group, Inc.
Lease Name Fr. Flanagans Boys Home A1-32 Well No. A 1-32
Office Address 1726 Champa St, Suite 600, Denver, Colo. 80202
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above
Section Plat

Dry Hole
Date Well completed April 1, 19 81
Application for plugging filed April 1, 19 81
Application for plugging approved April 1, 19 81
Plugging commenced 4:30 P.M. - April 1, 19 81
Plugging completed 6:15 P.M. - April 1, 19 81
Reason for abandonment of well or producing formation

o Dry Hole
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Duane Rankin
Producing formation Depth to top Bottom Total Depth of Well 2380'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				7"	965'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from feet to
feet for each plug set.

Filled hole with heavy mud.
Heavy mud to 975' with 20 sacks 50/50 Pozmix
through open ended drill pipe at 975', with heavy
mud to 300' with 20 sacks through open ended drill
pipe at 300'; with heavy mud to 40' with Howco plug
and 1/4 sack hulls with solid bridge at 40'; with
10 sacks to surface. Rig has no rathole.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company, P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.
Richard L. Mead (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) Richard L. Mead
Richard L. Mead, Vice President
P. O. Box 129, Sterling, Kansas 67579
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of April, 19 81.

My commission expires F. A. WUELLNER - NOTARY PUBLIC
My Appointment Expires Sept. 17, 1981

F. A. Wuellner, Notary Public.

RECEIVED
STATE CORPORATION COMMISSION

APR - 8 1981

CONSERVATION DIVISION
Wichita, Kansas

4-8-81

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG - - - - - FR. FLANAGANS BOYS HOME A 1-32
Located: C NW/4, Section 32-21S-19W, Pawnee County, Kansas

OWNER: Benson Mineral Group, Inc.
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: March 26, 1981
COMPLETED: April 1, 1981

TOTAL DEPTH: 2380'

LOG

CASING RECORD

0 - 110 Gravel
110 - 483 Shale and Gravel
483 - 973 Shale
973 - 1335 Shale and Lime
1335 - 1840 Shale
1840 - 2368 Lime and Shale
2368 - 2380 Lime

Ran 26 joints new 7" OD casing. 965.41'
set at 965' G.L. Cemented with 250
sacks 60/40 Pozmix with 2% gel and
3% cc. Plug down at 3:00 PM, 3-27-81,
by Sun Cementing.

Plugged.

Deviation Surveys: 3/4° at 973'
1 1/4° at 2105'