


B-185-19458-0000

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County, Sec. 16 Twp. 23 Rge. 14 (E) (W) X
Location as "NE/CNW%SW%" or footage from lines SE NW NW

Lease Owner Icer Addis
Lease Name Beaver Well No. 1
Office Address P. O. Box 519, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) D. & A.
Date well completed 10/6/63 19
Application for plugging filed 10/6/63 19
Application for plugging approved 10/6/63 19
Plugging commenced 10/6/63 19
Plugging completed 10/6/63 19
Reason for abandonment of well or producing formation -0-



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production -0- 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Paul Turpin
Producing formation -0- Depth to top -0- Bottom 862X -0- Total Depth of Well 4052' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Pipe				8 5/8"	275'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.
Rotary mud was used in filling hole to a depth of 270' were 1st plug was set using 25 sacks cement, filling hole to a depth of 40' were 2nd plug was set using 10 sacks cement and filling hole to surface.

RECEIVED
STATE CORPORATION COMMISSION

OCT 11 1963

CONSERVATION DIVISION
Wichita, Kansas

10-11-63

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor L. J. Dreiling & Sons, Inc.
Address Victoria, Kansas

STATE OF Kansas COUNTY OF Ellis, ss.
I, Leo F. Dreiling a contractor (employee of owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo F. Dreiling
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of October, 1963

My commission expires August 14, 1965
Ronald Zimmerman Notary Public.

L. J. DREILING and SONS, Inc.
VICTORIA, KANSAS

15-185-19458-0000

WELL LOG

Company Icer Addis
P. O. Box 519, Great Bend, Kansas

Sec. 16 Twp. 23 Rng. 11W

Farm Beaver No. 1

Location SE NW NW

Total Depth 4052'

County Stafford County, Kansas

Comm. 9/28/63 Comp. 10/6/63

Elevation: D. F. 1977 KB

Contractor L. J. Dreiling & Sons, Inc.
Victoria, Kansas

G. R.

Casing Record
275' - - - - 8 5/8"

Cement Record
200 sacks cement

Production:
D. & A.

Figures Indicate Bottom of Formations

0 - 130	Surface Clay & Sand
130 - 275	Shale
275 - 374	Shale & Shells
374 - 888	Shale & Shells
888 - 910	Anhydrite
910 - 1205	Shale
1205 - 1755	Shale
1755 - 1990	Shale & Lime
1990 - 2205	Lime & Shale
2205 - 2380	Lime & Shale
2380 - 2605	Lime & Shale
2605 - 2818	Lime & Shale
2818 - 3010	Shale & Shells
3010 - 3260	Lime & Shale
3260 - 3446	Lime & Shale
3446 - 3545	Lime
3545 - 3770	Lime
3770 - 3924	Lime
3924 - 4015	Lime
4015 - 4052	Lime
4052	TD

RECEIVED
STATE CORPORATION COMMISSION

OCT 11 1963

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS }
COUNTY OF ELLIS }

ss.

I, Leo F. Dreiling, of the L. J. Dreiling & Sons, Inc.
upon oath states that the above and foregoing is a true and correct
copy from the Daily Drilling Report from your Beaver No. 1.

Leo F. Dreiling
LEO F. DREILING

Subscribed and sworn to before me this 9th day of October, 1963.

Ronald Zimmerman
NOTARY PUBLIC

My Commission Expires: August 14, 1965