

R

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
5-23-77
MAY 23 1977
COURTESY OF DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15-145-20370-0000 (of this well)
Wichita, Kansas

Operator's Full Name Beren Corporation

Complete Address 970 Fourth Financial Center, Wichita, Kansas 67202

Lease Name Marlyn Well No. 2

Location NW NW NW Sec. 29 Twp. 21 Rge. (E) (W) 17

County Pawnee Total Depth 2064'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Kelso Pipe Pulling

Address Box 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour 2:30 P Day 19 Month 5 Year 1977

The above well was plugged as follows:

Total Depth 2064' 8 5/8 csg set 751' cwc 250 sk.

4 1/2 csg set 2063' cw 75 sk cem.

4 1/2 csg PBSD 2055' & perf. (2041'-2050')

Filled 4 1/2 csg W/sd (2055'-2000') dumped 3 sk cem W/dump bailer. (2000'-1970')

Cutoff & recovered 1740' of 4 1/2 csg.

Sun Cementing Co. mixed & pumped down 8 5/8 csg with 20 sk gel & water, released plug & 100 sk 60/40 poz & shutin.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Masney
Well Plugging Supervisor

DATE 5-24-77
WV. NO. 5205-W