

KANSAS

FORM CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGEN'T REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, Ks. 67202

API Number 15 145-20,692 (of this well)

Operator's Full Name BEREN CORPORATION

Complete Address 970 4th FINANCIAL CENTER-WICHITA, KANS.

Lease Name WAYNE Well No. #1

Location NE-SE-NW Sec 27 Twp. 21 Rge. 17 (E) (W) W

County PAWNEE Total Depth 3965 EF

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereafter indicated

Plugging Contractor STERLING DRILLING.

Address BOX 129-STERLING, KANS License No.

Operation Completed: Hour 2:00 ^{PM} Day 20 th Month SEPT Year 1980

The Above well was plugged as follows: w/100^{ft} 60/40 Perm - 2% GEL. 3% OH-CL.
8 5/8" 844^{EF} SD CUC w/350^{ft} HALLIBURTON LIGHT.
ORDERED 105^{ft} 50/50 Perm 4% GEL. + 8 5/8" PLUG.
SPOTTED WITH DRILL STEM- WITH HEAVY MUD BETWEEN ALL PLUGS.
1st PLUG. @ 800^{EF} w/60^{ft} CMT.
2nd PLUG. @ 270^{EF} w/30^{ft} CMT.
3rd PLUG. - ^{SOLID BRIDGE} HULLS + PLUG @ 40^{EF}. 0 w/10^{ft} CMT.
3^{ft} IN RAT HOLE.
2^{ft} IN MOUSE HOLE. CEMENTED BY HALLIBURTON CMT.

I hereby certify that the above well was plugged as herein stated.

RECEIVED
STATE CORPORATION COMMISSION
Signed: [Signature]
Well Plugging Supervisor

INVOICED
DATE 9-23-80
INV. NO. 3202W

SEP 23 1980
CONSERVATION DIVISION
Wichita, Kansas