

15.145-20366-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Northern Natural Gas Co.

Complete Address P. O. Box 872, Woodward, Oklahoma 73801

Lease Name Dipman Well No. 1

Location C SW/4 Sec. 12 Twp. 21 Rge. (E) (W) 18W

County Pawnee Total Depth 2140'

Abandoned Oil Well Gas Well XX Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Pawnee Well Service, Inc.

Address Great Bend, Kansas License No. 633

Operation Completed: Hour 4 P Day 24 Month 11 Year 1975

The above well was plugged as follows:

Total Depth 2140' 8 5/8 csg set 824' cwc 350 sk.

4 1/2 csg set 2139' cw 125 sk cem.

4 1/2 csg PFS (2064-2076-2078-2096)

Filled 4 1/2 csg W/sd (2140-2040) dumped 3 sk cem W/dump bailer.

Cutoff & recovered A/1650' of 4 1/2 csg.

Squeezed 8 5/8 csg with 25 sk gel & water W/100 lbs hulls -released plug & pumped

125 sk 60/40 poz cem. by Sun Cementing Co.

RECEIVED
STATE CORPORATION COMMISSION
DEC 3 1975
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo. Marney
Well Plugging Supervisor

DATE 12-03-75

INV. NO. 2338-W