

15-145-00517-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

FEB 28 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Sunray D-X Oil Co
Complete Address: Box 729 Great Bend, Kans
Lease Name Edeker Well No. 1
Location NW NW SE Sec. 2 Twp. 21 Rge. (E) (W) 19
County Pawnee Total Depth 4375
Abandoned Oil Well Gas Well Input Well SWD Well D & A x
Other well as hereafter indicated:
Plugging Contractor: Forbes Casing Pulling
Address: Great Bend, Kans License No. 49
Operation Completed: Hour 3PM Day 25 Month 2 Year 64

The Above well, was plugged as follows:

8 5/8" 376' circulated with cement - 4 1/2" 4374' with 150 sax cement - Perf 4225'
Sand to 4225', set 3 sax cement with dump bailer - pulled 3638' 4 1/2" to
550', circulated hole with heavy gel mud through 4 1/2" (29 sax gel), displaced
25 sax cement through 4 1/2" at 550', heavy mud to 200', displaced 25 sax cement
through 4 1/2" - heavy mud to 35', cement 35' to 0'.

Mudding and cementing by Sun Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE

2/28/64

INV. NO.

8914-W