

KANSAS

RP

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 17 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Mill Drilling Company

Complete Address: Box 349 Russell, Kansas 67665

Lease Name Idecker Well No. 1

Location NW SW SE Sec. 2 Twp. 21 Rge. (E) (W) 19

County Pawnee Total Depth 4283'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes casing Pulling Co.

Address: Box 221 Great Bend, Kansas 67530 License No. 49

Operation Completed: Hour 11A Day 15 Month 10 Year 1969

The Above well was plugged as follows:

Total ^uepth 4283' 8 5/8 csg set at 408' cwc

4 1/2 csg set at 4282' cw 150 sk cmt.

4 1/2 csg PBSD 4248' with top perf. (4218)

Filled 4 1/2 csg W/sd (4200-4248) Dumped 4 sk cmt W/dump bailer. (4160-4200)

Cutoff and recovered 2300' of 4 3/4 csg.

Pumped thru 8 5/8 plug container with 20 sk gel and 120 sk 50-50 poz cmt W/6% total gel.

Max. pres. 500 lbs. SI pres 500 lbs.

I hereby certify that the above well was plugged as herein stated.

Signed: *Geo F. Murray*
Well Plugging Supervisor

INVOICED

DATE 10/17/69

INV. NO. 665-u