

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAY 4 1965

5-4-65
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Sunray D X Oil Co
Complete Address: Box 729 Great Bend, Kans
~~xxxxxxxKans~~

Lease Name Latas Well No. 1

Location SW NE NE Sec. 5 Twp 21 Rge. (E) (W) 19

County Pawnee Total Depth 4420

Abandoned Oil Well Gas Well Input Well SWD Well D & A x

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling Co

Address: Great Bend, Kans License No. 49

Operation Completed: Hour 5PM Day 30 Month 4 Year 65

The Above well was plugged as follows:

8 5/8" 388' circulated with cement - 5 1/2" 4418' with 175 sax cement.

PB to 4385' perf 4313'.

~~Filled with sand to 4300', set 5 sax cement with dump bailer. pulled
2500' 5 1/2" to 620', circulated hole with heavy mud through 5 1/2" (22 sax Gel)
displaced 20 sax cement through 5 1/2" at 640', heavy mud to 240', displaced
20 sax cement through 5 1/2" at 340', heavy mud to 35', set bridge and 10 sax
cement to bottom cellar.~~

Mudding and cementing by Halliburton Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 5/4/65

INV. NO. 1100-w

Signed: Leon Perty
Well Plugging Supervisor