

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 25 1969  
CONSERVATION DIVISION  
Wichita, Kansas  
8-25-69

Operator's Full Name DNB Drlg., Inc. & Kathol Petr., Inc.

Complete Address 737 1st Nat'l Bank Bldg., Wichita, Kansas

Lease Name Canon "A" Well No. 1

Location SW NE Sec. 13 Twp. 21 Rge. (E) (W) 19

County Pawnee Total Depth 4310'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor DNB Drlg.

Address Wichita, Kansas License No.       

Operation Completed: Hour 7:30 P Day 20 Month 8 Year 1969

The above well was plugged as follows:

RTD 4310' 8 5/8 csg set at 282' cwc Cmt. Mat. 50-50 poz cmt W/6% total gel.  
Gunned pits, circulated heavy mud, set cementing plug at 480' and displaced 70 sk cmt  
thru drill pipe. Heavy mud to 270' set cementing plug and displaced 20 sk cmt thru  
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base  
of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8/26/69  
INV. NO. 369-W

Signed: [Signature]  
Well Plugging Supervisor