

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

Form CP-3  
Rev. 6-26-62  
RECEIVED  
STATE CORPORATION COMMISSION

FEB 6 1967

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Recod 3600'  
20941-85 (new)

Operator's Full Name Mull Drilling Company Inc.,

Complete Address: 1625 Wichita Plaza Wichita, Kansas

Lease Name Mezger Well No. 1

Location NW NW NE Sec. 11 Twp. 21 Rge. 19 (E) (W) X

County Pawnee Total Depth 4281'

Abandoned Oil Well X Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated:       

Plugging Contractor: Forbes Casing Pulling Inc.,

Address: Box 221 Great bend, Kansas License No. 49

Operation Completed: Hour 2:30 P Day 4 Month 2 Year 1967

The Above well was plugged as follows:

Total Depth 4281' 8 5/8 csg set at 248' cwc.

4 1/2 csg set at 4280' cwc 150 sc cement.

PR 4274' and perf. 4207'. Filled with sand to 4180' and dumped 4 sc cem.

with dump bailer.

Recov. 3600' of 4 1/2 csg.

Squeezed 8 5/8 csg with 20 sc gel mud and 85 sc cement.

Pump Pres. 350 lbs. Shut in pres. 200 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 2/7/67  
INV. NO. 4724-11

Signed: [Signature]  
Well Plugging Supervisor