

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

SEP 23 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Harter Oil Company

Complete Address: 1010 Shreveport-Barksdale Hwy Shreveport, Louisiana 71105

Lease Name Mezger Well No. 1

Location NW NE NE Sec. 11 Twp. 21 Rge. 19 (E) (W) X

County Pawnee Total Depth 4288'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Go. Tools By Allied Cement.

Address: Russell, Ks. License No.

Operation Completed: Hour 12:30P Day 20 Month 9 Year 1968

The Above well was plugged as follows:

Total Depth 4288' 8 5/8 csg set at 247' cwc 200 sc.

4 1/2 csg set at 4288' cw 300 sc. poz cement.

4 1/2 csg DV tool set at 1200' and cemented with 275 sc cement.

No pipe recov.

Pumped thru 4 1/2 swage with 30 sc gel, and 50 sc 50-50 poz cmt W/6% total gel.

Pumped thru annulus (8 5/8-4 1/2) with 85 sc 50-50 poz cmt W/6% total gel.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo P. Messing
Well Plugging Supervisor

INVOICED

DATE 9/23/68

INV. NO. 8495-105