

To: 1 120152
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 145-21,045-0000
C NW/4 , SEC. 25 , T 21 S, R 19 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5817
Operator: Benson Mineral Group, Inc.
Name &
Address 1536 Cole Boulevard, Suite 220
Golden, CO 80401

3960 feet from S section line
3960 feet from E section line
Lease Name Proffitt Well # 1-25
County Pawnee 76.05
Well Total Depth 2340 feet
Conductor Pipe: Size feet
Surface Casing: Size 7 feet 1008

Abandoned Oil Well Gas Well X Input Well SWD Well D&A
Other well as hereinafter indicated

Plugging Contractor Benson Mineral Group, Inc. License Number 5817
Address 1536 Cole Boulevard, Suite 220, Golden, CO 80401

Company to plug at: Hour: 11 a.m. Day: 10 Month: 10 Year: 1988

Plugging proposal received from William Philo
(company name) Benson Mineral Group, Inc. (phone) 303-232-0100

were: 4 1/2" casing at 2334' PBD 2322' Perfs at 2211-16'
1st plug pump 150 lbs. hulls and 70 sx cement in 4 1/2" casing.
2nd plug pump 40 sx cement between 7" & 4 1/2" casing.

RECEIVED
STATE CORPORATION COMMISSION
OCT 17 1988

10-17-88

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations Completed by Agent?: All X Part None
Operations Completed: Hour: 1 p.m. Day: 10 Month: 10 Year: 1988

ACTUAL PLUGGING REPORT 1st plug pumped in 4 1/2" casing with 200 lbs. hulls and 60 sx cement. Pumping pressure 0-600 psi and shut in 350 psi.
2nd plug pumped between 7" & 4 1/2" casing with 15 sx cement. Pumping pressure 0-650 psi and shut in 550 psi. Casing shut off.

Well never produced.

Remarks: Used Thrifty Mix 65/35 Pozmix 10% gel by B.J. Titan. No casing recovery.
(if additional description is necessary, use BACK of this form.)

(if desired, observe this plugging.)

INVOICED

DATE 10-27-88

Signed Duane Rankin (TECHNICIAN)

INV. NO. 22759

NOV 15 1988