

1 120153

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-145-21,059-0000

C N/2 SW/4, SEC. 24, T 21 S, R 19 W/EX
1980 feet from S section line

3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5817

Lease Name Rastrelli Well # 1-24

Operator: Benson Mineral Group, Inc.

County Pawnee 75.56

Name & Address 1536 Cole Boulevard, Suite 220

Well Total Depth 2325 feet

Golden, CO 80401

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 404

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Benson Mineral Group, Inc. License Number 5817

Address 1536 Cole Boulevard, Suite 220, Golden, CO 80401

Company to plug at: Hour: 1:30 p.m. Day: 10 Month: 10 Year: 1988

Plugging proposal received from William Philo

(company name) Benson Mineral Group, Inc. (phone) 303-232-0100

were: 4 1/2" at 2324' PBD 2290' Perfs at 2162-2222' (2 sets)

1st plug pump in 4 1/2" casing with 200 lbs. hulls and 70 sx cement,

2nd plug pump between 8 5/8" & 4 1/2" with 70 sx cement,

3rd plug pump between 8 5/8" & 4 1/2" casing with 50 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

OCT 17 1988

10-17-88

CONSERVATION DIVISION
Wichita, Kansas

Duane Rankin
(TECHNICIAN)

Plugging Proposal Received by _____

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3 p.m. Day: 10 Month: 10 Year: 1988

ACTUAL PLUGGING REPORT 1st plug pumped in 4 1/2" casing with 150 lbs. hulls and 50 sx cement. Pumping pressure 0-600 psi and shut in 300 psi.

2nd plug pumped between 8 5/8" & 4 1/2" with 150 lbs. hulls and 40 sx cement.

Pumping pressure 0-600 psi and shut in 250 psi.

Remarks: Used Thrifty Mix 65/35 Pozmix 10% gel by B.J. Titan. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED

(did / XXXX XXX) observe this plugging.

DATE 10-27-88

Signed Duane Rankin
(TECHNICIAN)

INV. NO. 22761

10-10 NOV 15 1988