

1 080325

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,124-0000
NE SE NW, SEC. 16, T 23 S, R 14 WEX
3630 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6039

Lease Name Beaver A Well # 1

Operator: L. D. Drilling, Inc.
Name & Address: R. R. 1, Box 183B
Great Bend, KS 67530

County Stafford 131.63
Well Total Depth 4050 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 430 ✓

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: noon Day: 18 Month: February Year: 19 85

Plugging proposal received from Bob Brenneman

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" set at 4049' PBTD 3910' Perfs at 3976-82, 3851-54'

1st plug sand back to 3800' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

release 8 5/8" rubber plug and pump 125 sx cement.

Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:15 pm Day: 18 Month: February Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 3800' and dumped 5 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement

10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 125 sx cement

RECEIVED STATE CORPORATION COMMISSION

FEB 25 1985

Maximum pressure 700 psi and shut in 500 psi

CONSERVATION DIVISION Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton. Recovered 2225' 5 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED

(did / ~~not~~) observe this plugging.

DATE 2-27-85

Signed J. A. [Signature] (TECHNICIAN)

INV. NO. 7169