

To: 1 120647  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 30517  
Operator: Turnco Drilling Inc.  
Name:  
Address: Box 771327  
Wichita, KS 67277-1329

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 12 p.m. Day: 19 Month: 11 Year: 19 91

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 5 1/2" at 3996' w/125 sx cement, PBTD 3989', Perfs at 3952-68'

1st plug sand back to 3898' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 5 sx gel, 250 sx cement with 100 lbs. hulls mixed in last 100 sx cement.

Plugging Proposal Received by Steve Durrant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 2 p.m. Day: 19 Month: 11 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3900' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 250 lbs. hulls, 5 sx gel, 100 sx cement, and an additional 150 sx cement with 150 lbs. hulls mixed in.

Pumping pressure 0-250 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 329' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

STATE CORPORATION COMMISSION

INVOICE RECEIVED  
DATE 12-5-91  
INV. NO. 33967 NOV 22 1991

Signed David Rankin  
(TECHNICIAN)