

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-115-21063-0000

SE/4, Sec. 12, T 21 S, R 2 #/E

330 feet from #/S section line

895 feet from #/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6030

Lease Name Taylor Well # 1

Operator: Ainsworth Operating Co.  
Name &

County Marion

Address Box 1269, 1255 Lake Ave.

Well Total Depth 2921 feet

Colorado Springs, Co  
80907

Conductor Pipe: Size 5 1/2 feet 2918 w/65 af

Surface Casing: Size 8 7/8 feet 202

Abandoned Oil Well X Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Crawford Well Service License Number 8349

Address Eldorado, Kansas

Company to plug at: Hour: Am Day: 9 Month: July Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO Kenneth Brooks

(company name) Ainsworth Operating Co. (phone) 316-752-3480 <sup>mobile</sup>

were: plug back w/gravel above perforations @ 285' to  
2800', cap w/6 af cement.

Henry McKee  
Signed Ralph Tittel  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part top None \_\_\_\_\_

Operations Completed: Hour: 4:45 Pm Day: 10 Month: July Year: 1984

ACTUAL PLUGGING REPORT After above was completed, recovered

1754' of 5 1/2 casing. Dreg mud in hole @ 245'  
Bailed dry to 265', Bridged hole @ 265' filled hole  
with 4 1/2 yds ready mix.

Remarks: Builders Concrete (newton) ticket # 5519.

PLUGGING SUMMARY--CASED WELLS

DATE 7-9-84 TIME 10:30 (AM) PM

OPERATOR Ainsworth Oper. Co.

OPER. LICENSE NO. 6030 API # 15-115-21063

PLUGGING CONT. Phillips Well Service

PLUGGING CONT. LICENSE NO. \_\_\_\_\_

PUSHER Squeek Brooks

PHONE NO. Mobil 316-752-3480, office 316-752-3534

FARM Taylor

WELL NO. 1 LEGAL SE/4 <sup>330 FSL</sup> <sub>825 FSL</sub> 12-21-2E

TD 2921 <sup>Hutton</sup> P.B.T.D. \_\_\_\_\_ C.P. \_\_\_\_\_ S.P. 202'-1755x

OTHER CASING 5 1/2" - 2918' W/ 65 SX. CEM.

PERFERATED AT 2856

LINER FROM \_\_\_\_\_ TO \_\_\_\_\_ W/ \_\_\_\_\_ SX. CEM.

MARKER DEPTH \_\_\_\_\_

BOTTOM PLUG sand back to 2800'

cap w/ 6 SX

CASING RECOVERY \_\_\_\_\_


TOP PLUG(S) no bridge at 275' fill w/ redi-  
mit

STARTING TIME afternoon 7/9/84 COMP. TIME 4:45 Pm

TECHNICIAN Nancy McKee 7/10/84  
Merlan Lunn

REPLACEMENT CARD


AINSWORTH OPERATING COMPANY 12-21-2E  
 P.O. BOX 1269 #1 TAYLOR 330' FSL &  
 COLORADO SPRINGS, CO 80901 825' FEL, SE/4  
 CONTR EDCO DRILLING CTY MARION  
 GEOL JAMES SMITH FIELD UNGER  
 ELV 1450 KB SPD 10/7/83 CARD ISSUED 1/26/84 IP OIL WELL  
 1444 GL DRLG COMP 10/11/83 HUNT 2858-2860  
 API 15-115-21,063



LOG	Tops	Depth/Datum
*LANS	.....	2051- 601
*BKC	.....	2427- 977
*MARM	.....	2436- 986
MISS	.....	2616-1166
KIND	.....	2702-1252
HUNT	.....	2855-1405
VIOLA	.....	2912-1462
RTD	.....	2921-1471
*SAMPLE TOPS		

8 5/8 " 202 / 175SX, 5 1/2 " 2918 / 65SX  
 DST (1) 2852-2864 (HUNT) / 30-30-30-30, REC 5' V SLI OCM,  
 SIP 19-19#, FP 19-19 / 19-19#  
 MICT - CO, CUT NOTCH (HUNT) 2856, AC 350 GAL (15%), SLI  
 SO, NON-COMMERCIAL, PF (HUNT) 2858-2860, W / 2 SPF, AC  
 500 GAL (15% MA), SLI SO, RE-AC 6000 GAL (15% NE), SLI SO,  
 POP (POTENTIAL NOT RPTD), 7/9/84

INFO RELEASED: 5/29/86 - WAS OIL WELL - TIGHT HOLE



**Specific Well--15-115-21063**

**All Well Data**

<b>API:</b> 15-115-21063 <b>KID:</b> 1002880265 <b>Lease:</b> TAYLOR <b>Well:</b> 1 <b>Original operator:</b> <b>Current operator:</b> Ainsworth Operating Co. <b>Field:</b> Unger <b>Location:</b> T21S R2E, Sec. 12 E2 SW SE SE 330 North, 825 West, from SE corner <b>Longitude:</b> -97.1552332 <b>Latitude:</b> 38.2339508 Lat-long calculated from footages <b>County:</b> Marion <a href="#">View well on interactive map</a>	<b>Permit Date:</b> <b>Spud Date:</b> Oct-07-1983 <b>Completion Date:</b> Feb-01-1984 <b>Plugging Date:</b> Jul-01-1984 <b>Well Type:</b> D&A <b>Total Depth:</b> 2921 <b>Elevation:</b> 1450 KB <b>Producing Formation:</b> <b>IP Oil (bbl):</b> <b>IP Water (bbl):</b> <b>IP GAS (MCF):</b> <b>KCC Docket No.:</b>
--	---

**Wireline Log Header Data**

<b>Logger:</b> Subterranean Logging, Inc. <b>Tool:</b> Radioactivity Log <b>Operator on log:</b> AINSWORTH DRILLING COMPANY <b>Top:</b> 2500; <b>Bottom:</b> 2914 <b>Log Date:</b> Oct-12-1983 <b>BHT:</b> F <b>Gamma Ray:</b> Y <b>Spontaneous Potental:</b> <b>Holdings at:</b> Lawrence	<ul style="list-style-type: none"> <li>• <a href="#">Download Black and White Scan</a> (Zip size: 276 k)</li> </ul>
For information on software to view and use the files we distribute on our web pages, please view our <a href="#">File Format Tools</a> page.	

**Information from Outside Sources**

**Please note:** The link below takes you away from the web site of the Kansas Geological Survey to the website of the Kansas Geological Society, a library in Wichita. The Survey can not help with information presented by the Walters Digital Library.

[From Kansas Geological Society's Walters Digital Library](#)

[Kansas Geological Survey, Oil and Gas Well Database](#)  
 Comments to [webadmin@kgs.ku.edu](mailto:webadmin@kgs.ku.edu)  
 URL=<http://www.kgs.ku.edu/Magellan/Qualified/index.html>  
 Well Display Program Updated Jan. 2008. Data added continuously.