

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-115- 21, 148-0000

SENESE, Sec. 35, T 21 S, R 4 W 1/2

1650 feet from N 1/4 section ~~line~~ ^{se c}

330 feet from W 1/4 section ~~line~~ ^{se c}

TECHNICIAN'S PLUGGING REPORT

Operator License # 5120

Lease Name SAUAGE Well # 1

Operator: Range Oil Co Inc.
Name & Address 220 West Douglas
Wichita Ks
67202

County MANION

Well Total Depth 2557 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 220

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Range Drilling Co Inc License Number 5124

Address Wichita Ks 67202

Company to plug at: Hour: 5:00 PM Day: 24 Month: Oct Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Tim Zulkowski

(company name) Range Drilling Co Inc (phone)

were: 40 SX @ 275'

20 SX @ 60'

10 SX in RH

60/40 Pos 2% CC

Signed

Jack Haley
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 5:30 PM Day: 24 Month: Oct Year: 19 84

ACTUAL PLUGGING REPORT 40 SX @ 275'

20 SX @ 60'


10 SX in R.H. 60/40 Pos 2% CC

Howco

749088

Remarks:

RANGE OIL COMPANY, INC. 35-21-4E
 220 W. DOUGLAS, 240 PAGE COURT #1 SAVAGE SE NE SE
 WICHITA, KS 67202
 CONTR RANGE DRILLING CO. CTY MARION
 GEOL BOB OLSEN FIELD FAIRPLAY EXT
 (T/4 S)
 ELV 1423 KB SPD 10/18/84 CARD ISSUED 11/8/84 IP D&A/HUNT
 1418 GL 10/24/84



SMP	Tops	Depth/Datum
BR LM	1713- 290
LANS	1768- 345
BKC	2126- 705
CONG	2266- 843
MISS CHT	2276- 853
MISS LM	2372- 949
KIND	2416- 993
HUNT	2544-1121
RTD	2557-1134

API 15-115-21,148
 8 5/8 " 220/175SX
 DST (1) 2262-92 (CONG) / 30-30-60-60, WB, REC 210' VSOCM
 (1% OIL), SIP 756-767#, FP 63-73 / 148-126#, BHT 104°



Specific Well--15-115-21148

All Well Data

API: 15-115-21148 KID: 1002880341 Lease: SAVAGE Well: 1 Original operator: Current operator: Range Oil Company, Inc. Field: Wildcat Location: T21S R4E, Sec. 35 SE NE SE 1650 North, 330 West, from SE corner Longitude: -96.9510767 Latitude: 38.1775313 Lat-long calculated from footages County: Marion View well on interactive map	Permit Date: Spud Date: Oct-18-1984 Completion Date: Oct-24-1984 Plugging Date: Oct-31-1984 Well Type: D&A Total Depth: 2557 Elevation: 1418 GL Producing Formation: IP Oil (bbl): IP Water (bbl): IP GAS (MCF): KCC Docket No.:
--	---

Wireline Log Header Data

Logger: Geologist's Report Tool: Drilling Time and Sample Log Operator on log: RANGE OIL Top: 300; Bottom: 2557 Log Date: Oct-25-1984 BHT: F Gamma Ray: Spontaneous Potential: Holdings at: Lawrence	<ul style="list-style-type: none"> • Download Black and White Scan (Zip size: 292 k)
For information on software to view and use the files we distribute on our web pages, please view our File Format Tools page.	

Cuttings Data

Box Number: B8632 Starting Depth: 300 Ending Depth: 2000
Box Number: B8633 Starting Depth: 2000 Ending Depth: 2557

Information from Outside Sources

Please note: The link below takes you away from the web site of the Kansas Geological Survey to the website of the Kansas Geological Society, a library in Wichita. The Survey can not help with information presented by the Walters Digital Library.