

State of Kansas



15-185-30341-0000

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

11-21-64

RECEIVED
STATE CORPORATION COMMISSION

NOV 21 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Clyde Merckle of Lauck Drilling Co., Inc. has this date requested permission to plug the following described well:

Mr. Merckle guarantees payment of the plugging fee.

Operator's full Name: D. R. Lauck Oil Company, Inc.

Complete Address: 301 South Broadway, Wichita, Kansas

Lease Name: Keller Well No. # 1

Location: SE NE SE Sec. 9 Twp. 22 Rge. 13 (E)(W) W

County Stafford Total Depth 3851' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Merckle was instructed to plug the well as follows:

263' of 8 5/8" surface pipe, cement circulated with 220 sacks. Fill hole with drilling mud to 240', 1st cementing plug, bridge with 1/2 sack of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10 sacks to base of the cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Arlene Elving
Conservation Division Agent