



ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION  
 OCT 21 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Woolridge of Pan American Petro. has this

date requested permission to plug the following described well:

Mr. Woolridge guarantees payment of the plugging fee.

Operator's full Name: Pan American Petroleum Corporation

Complete Address: Box 432, Liberal, Kansas

Lease Name: F. Finnup Well No. 1

Location: NE NW Sec. 3 Twp. 23 Rge. 33 ~~(E)~~ (W)

County: Finney Total Depth 4900' Oil Well X

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Woolridge was instructed to plug the well as follows:

8 5/8" to 568' circulated w/ cement. 4 1/2" to 4855' cemented.


Top perforations 3790' Plug bottom w/ 20 sacks cement.

Top of cement 3494' Mud 3494' to 550'

Spot 35 sacks cement 550' to 450' Mud 450' to 45'

Blug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,

  
 Conservation Division Agent