

15-055-20478-0000

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Finney SEC. 1 TWP. 23S RGE. 31W E/W
 Location as in quarters or footage from lines:
SE SE NE

Lease Owner Plains Resources, Inc.
 Lease Name Janof Trust Well No. 1
 Office Address 2200 Classen Blvd., Ste. 2000, Okla. City, OK 73106
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
 Date Well Completed: 8-14-81
 Application for plugging filed 9-1-81
 Plugging commenced 8-15-81
 Plugging completed 8-15-81
 Reason for abandonment of well or producing formation No economical shows

Locate Well
 correctly on above
 Section Platt.

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas
 Producing formation None Depth to top _____ bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Surface				8 5/8"	587'	None

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

60 sx cmt from 980' to 730'
40 sx cmt from 550' to 400'
10 sx cmt from 40' to surface

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Ramco Drilling; Halliburton

STATE OF Oklahoma COUNTY OF Oklahoma, ss.
Carl F. Pomeroy (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) Carl F. Pomeroy
Carl E. Pomeroy, Production Mgr.
 (Address)
 (same as above)

SUBSCRIBED AND SWORN TO before me this 9th day of Sept., 19 81

Ann Oliver Smith
 Notary Public.

My Commission expires: 4/6/82

RECEIVED
 STATE CORPORATION COMMISSION

9-3-81

SEP - 3 1981

CONSERVATION DIVISION
 Wichita, Kansas

W E L L L O G

RECEIVED
STATE CORPORATION COMMISSION

WELL NAME: Janof Trust #1

OPERATOR: Plains Resources, Inc.

SPUD DATE: 8-3-81

CONTRACTOR: Ramco Drilling Company

COMPLETION DATE: 8-15-81

CASING: 8 5/8, 24# New Kaset @ 587' w/250
sx light cmnt, 2 % cc, 1/4 flow
seal, 155 sx Class A, 3% cc

LOCATION: C SE SE SE
Sec. 1-23S-31W
Finney County, Ks.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Surface	0	538
Shale	538	1420
Shale	1420	1551
Sand	1551	1767
Shale	1767	2270
Shale and Sand	2270	2570
Shale	2570	2880
Shale and Lime	2880	3075
Lime and Shale	3075	3379
Lime	3379	3730
Lime and Shale	3730	4072
Shale	4072	4250
Lime and Shale	4250	4420
Lime	4420	4535
Shale and Sand	4535	4625
Lime	4625	4705
Lime and Shale	4705	4970
RTD	4970	


STATE OF KANSAS
COUNTY OF SEDGWICK

I certify that the above information is true and correct to the best of my knowledge.

THE RAMCO DRILLING CORPORATION

By: J. V. [Signature]

Subscribed and sworn to before me on this 21st day of September, 1981.

 JUANITA L. BOTKIN
STATE NOTARY PUBLIC
Sedgwick County, Kansas
My Appt. Exp. 6-30-83

Juanita L. Botkin
Notary Public

My Appointment Expires: