

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-185-21,893-0000

LEASE NAME Copeland

WELL NUMBER #2

2310 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 2 TWP 23 RGE. 14 (E) or (W)

COUNTY Stafford

Date Well Completed _____

Plugging Commenced 11-19-88

Plugging Completed 11-28-88

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Woodman-Iannitti Oil Co.

ADDRESS Box 308, Great Bend, Kansas 67530

PHONE# (316)-792-1922 OPERATORS LICENSE NO. 6588

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on November 21, 1988 (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? With application

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3962'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	216'	None
				5-1/2"	3961'	1,998.40'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set. Dumped sand to 3580' and 5 sacks cement. Shot casing at 3300', 2700', 2500', 2300' & 2000'. Pulled 54 joints of 5-1/2" casing. B.J. Titan plugged well with 300# hulls 10 sacks gel, 50 sacks 60/40 pozmix cement with 6% gel, 10 sacks gel, 100# hulls. Released plug and pumped 100 sacks cement. Max press 400 psi and shutin 100 psi. (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Woodman-Iannitti Oil Co.

STATE OF Kansas COUNTY OF Barton, ss.


James W. Rockhold (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold

(Address) Box 698, Gt. Bend, Ks. 67530

DESCRIBED AND SWORN TO before me this 5th day of December, 1988

Iona M. Leatherman
 Notary Public



My Commission Expires:

RECEIVED
 STATE CORPORATION COMMISSION
 UEL 6 1988
 12-6-88
 CONSERVATION DIVISION
 Wichita, Kansas