

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Stafford County, Sec. 2 Twp 23S Rge. 14W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
SE SW SW

Lease Owner Graves Drilling Company, Inc.
Lease Name Copeland Well No. 1

Office Address 910 Union Center Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole)

Dry Hole

Date Well completed 7-10-79 19
Application for plugging filed 7-10-79 19
Application for plugging approved 7-10-79 19
Plugging commenced 2:00 A. M. 7-11-79 19
Plugging completed 2:45 A. M. 7-11-79 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Wm T. Owen
Producing formation Depth to top Bottom Total Depth of Well 3578'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud To 540' 40 Sacks 50-50 Posmix
Mud To 240' 40 Sacks 50-50 Posmix
Mud To 40' 12 Sacks 50-50 Posmix
3 Sacks In Rat Hole

RECEIVED
STATE CORPORATION COMMISSION

JUL 20 1979 7-20-79

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Merckle Drilling Co.

STATE OF Kansas COUNTY OF Barton, ss.
Clyde Merckle (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Clyde Merckle


(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of July, 1979

Loretta Barry

Notary Public.

My commission expires 3-28-80



15-185-20926-0000

Graves Drilling Co., Inc.
910 Union Center
Wichita, Kansas 67202


Copeland #1

SE SW SW Section 2 23 South 14 West

Stafford County

Driller's Log - Total 3578

0 - 160	Sand
160 - 275	Shale
275 - 320	Red Bed
320' - 420	Sand
420 - 873	Red Bed
873 - 896	Anhydrite
896 - 1900	Red Bed and Shale
1900 - 2660	Lime and Shale
2660 - 3395	Lime and Shale
3395 - 3578	Lime


Clyde Merckle

RECEIVED
STATE CORPORATION COMMISSION
JUL 20 1979
CONSERVATION DIVISION
Wichita, Kansas