


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

15-185-00228-0000

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Stafford County, Sec. 2 Twp. 23 Rge. 14W (E) (W)
Location as "NE/CNWxSWx" or footage from lines NW/ SW/ SW/
Lease Owner Morgenstern & Specter
Lease Name Copeland Well No. I
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 1-13-53 19__
Application for plugging filed June 14, 1960 19__
Application for plugging approved June 15, 1960 19__
Plugging commenced 6/17/60 19__
Plugging completed 6/23/60 19__
Reason for abandonment of well or producing formation failure to produce
profitably
If a producing well is abandoned, date of last production May, 1960 19__
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot, St John, Kansas
Producing formation Kansas City Depth to top 3520 Bottom 3847 Total Depth of Well 4050 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 3/4" OD	204 ft.	none
				5 1/2" OD	3756	2776 feet

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back with sand to 3370 feet. Dumped 5 sacks Cement.
Pumped 38 barrels Mud. 75 sacks Cement.

RECEIVED
STATE CORPORATION COMMISSION

JUL 11 1960

CONSERVATION DIVISION
Wichita, Kansas

7-11-60

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor E. & L. CASING PULLING COMPANY, NO. 377
Address GREAT BEND, KANSAS

STATE OF Kansas, COUNTY OF Russell, ss.
Morgenstern & Specter, Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Russell, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 25th day of June, 1960

My commission expires March 9, 1962
W. D. Dawson Notary Public.



WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


COPY
15-185-002280000

Company: WESTGATE-GREENLAND OIL COMPANY
Farm: Copeland No. 1

SEC. 2 T. 23 R. 14W
NW SW SW

Total Depth. 4050 RB
Comm: 12-26-52 Comp. 1-13-53
Shot or Treated.
Contractor. Westgate Drlg. Corp.
Issued. 3-21-53

County Stafford
KANSAS



CASING:

10 3/4" 204' cem. w/160 sx
7" 3758' cem. w/150 sx

Elevation. 1954 DF

Production. 25 BO Temp.

Figures Indicate Bottom of Formations.

sand	115
shale & shells	204
shale	300
sand & shale	425
shale & red bed	863
anhydrite	885
shale & shells	1130
salt & shale	1400
shale & shells	1700
lime & shale	1840
lime.	2025
lime & shale	2170
lime	2275
lime & shale	3545
lime	3750
shale & lime	3863
shale, lime w/chert	3891
simpson	3898
shale	3950
arbuckle	4050 RB
Total Depth	

Tops: DF	
Anhydrite	861
Heebner	3374
Brown Lime	3505
Lansing	3520
Viola	3848
Simpson	3889
Arbuckle	3942

DST: 3630-51' open 1 hr.
gas to surface in 59 mins.
rec. 150' froggy oil, 30 feet
heavily oil & gas cut mud 30'
oil & gas cut mud FFP 110#
30' slightly oil & gas cut
mud, BHP 1225#.

DST: 3653-3695, open 1 hr. good
blow, rec. 530' gas cut salt
water-slight show of oil, FFP
230#, BHP 1010#.

DST: 3944-53, open 1 hr. 900'
sulphur water, FFP 60# FFP 410#,
BHP 1220#.

Schlumberger run
Perforated 48 shot 3640-50, swab
3/4 BOPH & show water.
1000 GA, swabbed 75 BO in 4 hrs.