

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-185-22,041-0000

LEASE NAME Devore

WELL NUMBER "C" #3

3630 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 3 TWP. 23 RGE. 14 (E) or (W)

COUNTY Stafford

Date Well Completed _____

Plugging Commenced 3-3-89

Plugging Completed 3-20-89

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Oil Producers, Inc. of Kansas

ADDRESS Box 8647, Wichita, Kansas 67208

PHONE # (316)-672-3440 OPERATORS LICENSE NO. 8061

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? March 20, 1989

Which agent did you notify? Steve Pfeiffer

Is AGO-1 filed? _____ If not, is well log attached? With application

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3998'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

3-22-89

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	342'	None
				4-1/2"	3996'	2,771.70'

RECEIVED
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION
 WICHITA, KANSAS
 MAR 22 1989

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Dumped sand to 3590' and 4 sacks cement. Shot casing at 3400'-3000' and 2700'. Pulled 65 joints of 4-1/2" casing. Howco plugged well with 300# hulls, 10 sacks gel, 50 sacks cement 10 sacks gel, 100# hulls and 100 sacks 60/40 pozmix cement with 6% gel. Maximum pressure was 500 psi and shutin 200 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold

(Address) James W. Rockhold
Box 698, Great Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 21st day of March, 1989

STATE NOTARY PUBLIC
 IONA M. LEATHERMAN
 Barton County, Kansas
 My Appt. Exp. 7-26-91

Iona M. Leatherman
 Notary Public

My Commission Expires: