

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-21.854-0000

LEASE NAME Allender

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER #3

660 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 3 TWP. 21S RGE. 14W (E) or (W)

LEASE OPERATOR Condor Energy

COUNTY Stafford

ADDRESS PO Box 108

Date Well Completed 12-83 or 1-84

PHONE (316) 792-1340 OPERATORS LICENSE NO. 6016

Plugging Commenced 8-9-94

Character of Well OIL

Plugging Completed 8-26-94

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on July 1994 (date)

by Case Morris (KCC District Agent's Name)

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation KC Depth to Top 3647 Bottom 3653 T.D. 3927

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
KC	OIL	GL	3941	4 1/2"	3941	1900

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Spot sand to 3590' and cement with 4sks cement on top sand with dump bailer. cut casing at 1990' and pulled all casing. Had Allied Cementing pump 300lbs hulls, 10sks jell, 50sks cement, 10sks jell, 100lbs hulls, wiper plug and 125sks cement. Cement being 60/40 6%.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Peters Drilling Co. License No. 03400

Address PO Box 742 Great Bend KS.

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Peters Drilling Co.

STATE OF Kansas COUNTY OF Barton, ss. 9-6-94


Michael G. Peters

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Michael G. Peters

(Address) PO Box 742 Great Bend KS



SUBSCRIBED AND SWORN TO before me this 30th day of August, 19 94

Connie R. Nelson
Notary Public

My Commission Expires: 11-11-94

15-185-21854-0000

RECEIVED
STATE CORPORATION COMMISSION

THE ROXANA CORPORATION

P.O. BOX 1850

#3 ALLENDER

3-23-14W

SE NE SE

GREAT BEND, KS 67530

CONTR LOBO DRG. CO.

CTY STAFFORD

AUG 10 1994

GEOL

FIELD GREEN VALLEY

+	+
+	+
+	+

CONSERVATION DIVISION
WICHITA, KANSAS

ELV 1956 KB SPD 12/1/83

CARD ISSUED 2/2/84

IP P 20 BO & 3.6 BWPD

1951 GL

LKC 3647-3653

API 15-185-21,854-0000

-169

LOG	Tops	Depth/Datum
ANH	855+1101
HEEB	3376-1420
TOR	3397-1441
DOUG	3412-1456
BR LM	3508-1552
LANS	3524-1568
BKC	3756-1800
VIOLA	3860-1904
SIMP	3895-1939
LTD	3938-1982
RTD	3942-1986

8 5/8 " 409/300 SX; 4 1/2 " 3941/200 SX
 DST (1) 3642-65 (LKC) / 45-?-45-?, 2800' GIP, REC 90'
 HOCGM, 120' VSMCGO, SIP 691-642#, FP 55-75 / 95-111#, HP
 1956-1902#
 MICT - CO, PF (LKC) 3647-53, W/2 SPF, AC 500 G, SWB LD, R &
 T, POP, P 20 BO & 3.6 BWPD, 1/23/84

(Handwritten mark)

COPYRIGHT 1983
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS