

LEASE NAME Allender

WELL NUMBER #1

660 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 3 TWP. 23S RGE. 14W (E) or (W)

COUNTY Stafford

Date Well Completed 6-3-82

Plugging Commenced 8-19-94

Plugging Completed 8-26-94

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Condor Energy

ADDRESS PO Box 108

PHONE# (316) 792-1340 OPERATORS LICENSE NO. 6016

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on JULY 1994 (date)

by Case Morris (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation KC & Viola Depth to Top 3871 Bottom 3875 T.D. 3980

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From GL	To	Size	Put In	Pulled out
KC	OIL		3999	4 1/2"	3999	1950'
Viola	OIL					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Spot sand to 3810' and run 4sk. cement on top of sand with dump bailer. Cut casing and pulled 1950' casing. Had Allied Cementing pump 300 lbs. hulls, 10sk. jell, 50sk. cement, 10sk. jell, 100lb. hulls, put in wiper plug and pump 125sk. cement. Cement being 60/40 6%.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Peters Drilling Co. License No. 37400

Address PO Box 742 Great Bend KS.

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Peters Drilling Co.

STATE OF Kansas COUNTY OF Barton, ss.

Michael G. Peters (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



(Signature) Michael G. Peters

(Address) PO Box 742 Great Bend KS

SUBSCRIBED AND SWORN TO before me this 30th day of August, 19 94

Connie R. Nelson
Notary Public

My Commission Expires: 11-11-94



15-185-21588-0000

DRILLERS WELL LOG

DATE COMMENCED: April 19, 1982
DATE COMPLETED: April 27, 1982

Roxana Corp.
ALLENDER #1
SE NE SE
Sec. 3, T23S, R14W
Stafford County, Ks.

ELEVATION: 1957 K.B.

0 - 845'	Surface Soil, Shells, Sand, Red Bed
845 - 872'	Anhydrite
872 - 3379'	Shale & Lime, Red Bed
3379 - 3400'	Shale
3400 - 3415'	Lime
3415 - 3512'	Shale
3512 - 3528'	Lime & Shale
3528 - 3846'	Lime
3846 - 3904'	Chert
3904 - 3947'	Sand
3947 - 4000'	Dolomite
4000'	R.T.D.

FORMATION DATA

Anhydrite	845'
Heebner	3379'
Toronto	3400'
Douglas	3415'
Br. Lime	3512'
Lansing	3528'
Viola	3846'
Simpson	3904'
Arbuckle	3947'
RTD	4000'

Surface Pipe: Set new 8-5/8",
23# pipe at 427' w/300 sacks
60/40 pozmix, 2% gel 3% cc.

Production Pipe: Set new 4 1/2",
10 1/2# pipe at 3999' w/175 sacks
60/40 pozmix, salt sat. w/15
Bbls. salt flush ahead.

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss

Ervin Neighbors of lawful age, does swear and state that the facts and
statements herein are true and correct to the best of his knowledge.

Ervin Neighbors

Subscribed and sworn to before me this 30 day of April 1982.

My Comm. Expires:
4-29-1986

Christy M. Dugan
Notary Public

RECEIVED
STATE CORPORATION COMMISSION
AUG 1 2 1994
CONSERVATION DIVISION
WICHITA, KANSAS