

15-185-00690-00-01

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Stafford SEC. 3 TWP. 23 RGE. 14W E/W
 Location as in quarters or footage from lines:
NW NW SE

Lease Owner The Roxana Corporation
 Lease Name Allender (OWWO) Well No. #2
 Office Address Box 1162, Great Bend, Ks. 67530
 Character of Well (Completed as Oil, Gas or Dry Hole): Oil
 Date Well Completed _____
 Application for plugging filed Yes
 Plugging commenced October 20, 1983
 Plugging completed October 27, 1983
 Reason for abandonment of well or producing formation _____

Locate Well
 correctly on above
 Section Platt.

Depleted
 Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well J. H. Metz
 Producing formation _____ Depth to top _____ bottom _____ T.D. 4010'
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	388'	None
				4 1/2"	4009'	2474.24'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Dumped sand to 3850' and 4 sacks cement. Shot casing at 3500' and 3300'
Shot casing at 3000', 2800' and 2650'. Shot casing at 2500' Pulled 37
JOINTS. Pulled 62 joints. 4 1/2" casing. Squeezed well with 3 sacks hulls,
15 sacks gel, 50 sacks cement, 10 sacks gel, 1 sack hulls, released plug-
and pumped 120 sacks 60/40 Pozmix cement with 2% added gel and 3% calcium
chloride.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rockhold Engineering, Inc.
Box 698, Great Bend, Kansas 67530


STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold
Box 698, Great Bend, Ks 67530
 (Address)

SUBSCRIBED AND SWORN TO before me this 31st day of October, 1983

My Commission expires:



Iona M. Leatherman
 Notary Public.

