

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

Stafford County, Sec. 3 Twp. 23S Rge. 14 (E) W (W)

Location as "NE/CNW/SW" or footage from lines. NW NW SE

Lease Owner W. J. Coppinger, Etal

Lease Name Asher Well No. 1

Office Address Union National Building, Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed September 22 19 57

Application for plugging filed " 19 "

Application for plugging approved " 19 "

Plugging commenced " 19 "

Plugging completed " 19 "

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundage, Box 283, Hoisington, Kansas

Producing formation None Depth to top Bottom Total Depth of Well 3985 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Hole	Water	0	393	8 5/8"	387.87'	None
See Attached Log						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud from 3985' to 240': Dumped 20 Sacks of cement on Plug at 240':

Filled with mud to 20': Dumped 5 Sacks of cement on Plug at 20':

Filled to surface.

*Read  
9-26-57*

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rex & Morris Drilling Company

Address Box 334, El Dorado, Kansas

STATE OF Kansas, COUNTY OF Butler, ss.

O. E. McClure (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *O. E. McClure*

Box 334, El Dorado, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 25th day of September, 19 57

My commission expires July 23, 1960

*Winifred E. Cruit*  
Winifred E. Cruit Notary Public.

PLUGGING  
FILE SEC. 3 T. 23 R. 14W  
BOOK PAGE 48 LINE 19

ASHER WELL # 1

15-185-00690-0000-

W. J. COPPINGER, ET AL

Total Depth	- 3985	Location	- NW NW SE
Contractor	- Rex & Morris Drilling Co.	Section	- 3-23S-14W
Commenced	- 9-13-57	Stafford County, Kansas.	
Completed	- 9-23-57		
Initial Production	- D & A		

Casing Record:

8.5/8" @ 387.87' w/ 250 sacks

FORMATION	DEPTH
Surface Hole	393
Red Bed & Shale	860
Anhydrite	890
Red Bed & Shale & Shells	1520
Shale & Shells	1710
Lime & Shale	3108
Shale & Lime	3275
Lime & Shale	3470
Shale & Lime	3521
Lime	3740
Lime & Shale	3905
Shale & Sand	3951
Lime	3985

R. T. D.

I hereby certify the foregoing statements are true and correct to the best of my knowledge and belief.

Rex & Morris Drilling Company

By Paul W. Koonz

Title Geologist

STATE OF KANSAS )  
 ) SS.  
 COUNTY OF BUTLER )

Subscribed and sworn to before me, a Notary Public, this 25<sup>th</sup> day of September 1957.

Winifred E. Cruik  
Winifred E. Cruik - Notary Public

My commission expires:

July 23, 1960.

PLUGGING  
 FILE SEC 3 T 23 R 14W  
 BOOK PAGE 48 LINE 19