

STATE OF KANSAS
STATE CORPORATION COMMISSION
100 S. Market, Room 2078
Topeka, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-185-21280-0000

API NUMBER Drilled 4-25-81

LEASE NAME Link

WELL NUMBER 3

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 4 TWP. 23S RGE. 14W (E) or (W)

COUNTY Stafford

Date Well Completed

Plugging Commenced 8-11-97

Plugging Completed 10-7-97

RECEIVED
KANSAS CORP COM

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

1997 OCT 10 10:10 AM
10-10-97

LEASE OPERATOR Midwest Investment Co., Inc.

ADDRESS 2263 N. Janssen Chicago, IL. 60614

PHONE (773) 407-6716 OPERATORS LICENSE NO. 31995

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4021'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	424'	None
				4-1/2"	4020'	3000'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each section. Plugged off bottom with sand to 3850' and 4 sacks cement. Shot pipe loose @3000', layed down 4-1/2" casing. Plugged with 300# hulls, 10 sks. gel, 50 sks. cement, 10 sks. gel, 100# hulls, plug and 125 sks. cement, 60/40 pos, 6% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524.

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Midwest Investment Co., Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) *Mike Kelso*

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 9th day of October, 1997

Jane S. [Signature]
Notary Public

My Commission Expires:

