

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-21,258-0000

LEASE NAME Fox

WELL NUMBER "B" #1

2970 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 4 TWP. 23 RGE. 14 (E) or (W)

COUNTY Stafford

Date Well Completed _____

Plugging Commenced 9-16-91

Plugging Completed 9-30-91

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Iannitti Oil Co.

ADDRESS Box 308, Great Bend, Kansas 67530

PHONE# (316) 792-1922 OPERATORS LICENSE NO. 30395

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on September 30, 1991 (date)

by Duane Rankin (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, Is well log attached? With application

Producing Formation _____ Depth to Top _____ Bottom T.D. 3972'

Show depth and thickness of all water, oil and gas formations.

10-02-91

RECEIVED

OIL, GAS OR WATER RECORDS

CASING RECORD

STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	437'	None
				5-1/2"	3970 1/2'	2,030.87'

OCT 02 1991

REGISTRATION DIVISION
WICHITA, KANSAS

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Dumped sand to 3900' and 5 sacks cement. Shot casing at 3016', 2541', 2213' and 2039'. Pulled 59 joints of 5-1/2" casing. BJ Services plugged well with 300# hulls, 10 sack gel, 50 sacks cement, 10 sacks gel, 100# hulls, plug and 125 sacks 60/40 pozmix with 6% gel. Maximum pressure was 700 psi and shutin 500 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Iannitti Oil Co.

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold

James W. Rockhold

(Address) Box 698, Great Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 1st day of October, 1991

Iona M. Leatherman

Notary Public

My Commission Expires:

