

LEASE NAME Oscar Miller

WELL NUMBER 1

4950 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 4 TWP. 23S RGE. 14W (E) or (W)

COUNTY Stafford

Date Well Completed 2-16-54

Plugging Commenced 9-23-99

Plugging Completed 9-23-99

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Tengasco, Inc

ADDRESS P. O. Box 458 Hays, Kansas 67601

PHONE# (785) 625-6374 OPERATORS LICENSE NO. 32278

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9-20-99 (date)

by Richard Lacy (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation Simpson-Viola- L-KC Depth to Top 3693 Bottom 3943.5 T.O. 3960

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Simpson	Oil, Gas, Water	3933	3945	8 5/8"	229	None
Viola	" " "	3864	3900	5 /12"	3975	@006'
L-KC	" " "	3528	3756			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
Shot off Pipe at 2000'. Pulled up to 900'- Mixed 50 SX. 60/40 Poz Mix, 6% Gel
and displace to 900'. Pulled up to 270' and mixed 50 SX. of the same and
displaced. Pulled up to 40' and mixed 10 SX. of same and circulated cement
into cellar

Name of Plugging Contractor Allied Cementing

Address Great Bend, Kansas

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Tengasco, Inc.

STATE OF KANSAS COUNTY OF ELLIS, ss.


Terry W. Presker (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Terry W. Presker


(Address) P. O. Box 458, Hays, Kansas 67601

SUBSCRIBED AND SWORN TO before me this 4th day of Oct., 19 99

Linda K. Pfannenstiel
Notary Public



My Commission Expires: 2/5/2000
USE ONLY ONE SIDE OF EACH FORM



Form 9-1
Revised 05-88

RECEIVED
STATE CORPORATION COMMISSION
License No. 10-5-99
OCT - 5 1999
CONSERVATION DIVISION
Wichita, Kansas

ALLIED CEMENTING CO., INC. 2986

Federal Tax I.D.# 48-0727860

15-185-00693-00-01

TO P.O. BOX 31
RUSSELL, KANSAS 67665

SEP 30 1999

SERVICE POINT:
GREAT BEND

DATE <u>09-23-99</u>	SEC. <u>4</u>	TWP. <u>23E</u>	RANGE <u>14W</u>	CALLED OUT <u>11:30/AM</u>	ON LOCATION <u>12:45/PM</u>	JOB START <u>1:15/PM</u>	JOB FINISH <u>5:00/PM</u>
LEASE <u>MILLER</u>	WELL# <u>1</u>	LOCATION <u>K-9 + PADIUM RD 5S 1/2E</u>			COUNTY <u>STAFFORD</u>	STATE <u>KS</u>	
OLD OR NEW (Circle one) <u>NEW</u>				<u>3.5 SAE</u>			

CONTRACTOR Quality Well Service OWNER TENGASCO INCS

TYPE OF JOB PLUG HOLE PULLING

HOLE SIZE 7 7/8" T.D. 3974' CEMENT

CASING SIZE 5 1/2" DEPTH 3973' AMOUNT ORDERED 110 cu ft 60/40 Poz

TUBING SIZE DEPTH 6% GEL + 10% GEL

DRILL PIPE DEPTH USED ALL MATERIAL

TOOL DEPTH

PRES. MAX	MINIMUM	COMMON	<u>666</u>	@	<u>6.35</u>	<u>419.10</u>
MEAS. LINE	SHOE JOINT	POZMIX	<u>44</u>	@	<u>3.25</u>	<u>143.00</u>
CEMENT LEFT IN CSG.		GEL	<u>16</u>	@	<u>9.50</u>	<u>152.00</u>
PERFS.		CHLORIDE		@		
DISPLACEMENT				@		

EQUIPMENT

PUMP TRUCK	CEMENTER	<u>BIRD</u>				
# <u>181</u>	HELPER	<u>BIRD</u>				
BULK TRUCK			HANDLING	<u>110</u>	@	<u>1.05</u>
# <u>342</u>	DRIVER	<u>RICK</u>	MILEAGE	<u>27</u>	@	<u>118.80</u>
BULK TRUCK			COMMISSION			
#	DRIVER					

OCT - 5 1999

TOTAL \$ 948.40

REMARKS:

CONSERVATION DIVISION
Wichita, Kansas

SERVICE

1st Plug 5 1/2" CGG HANGING AT

900' Mill. 60/40 Poz. 6% GEL Displace & Balance

2nd Plug 5 1/2" CGG AT 2707' Mill

500' 60/40 - 6% Displace & Balance

Top Plug 7/8" Mill 1100' (over into

Cement sets (2000')

1cc AA Richard Perry tube

TOTAL \$ 526.95

CHARGE TO: TENGASCO INCS.

STREET P.O. Box 458

CITY HAYS STATE KS ZIP 67601

FLOAT EQUIPMENT

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX \$ 82.05

TOTAL CHARGE \$ 1562.40

DISCOUNT \$ 295.07 IF PAID IN 30 DAYS

SIGNATURE Joseph E. Mae Joseph E. Mae

PRINTED NAME

Net \$ 1267.33