

15.083-10324-0000

Form CP-3  
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 13 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Operator's Full Name El Dorado Supply Company

Complete Address: 764 Oil Hill Road, El Dorado, Kansas 67042

Lease Name Lee "S" Well No. 1

Location C NW NW Sec. 26 Twp. 21 Rge. 25 ~~(W)~~ (W)

County Hodgeman Total Depth 4584'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: None

Plugging Contractor: Southwest Casing Pulling Co.

Address: Box 364, Great Bend, Kansas License No. 399

Operation Completed: Hour 7:00 PM Day 11 Month 9 Year 1968

The Above well was plugged as follows:

8 5/8" to 257' circulated w/ cement. 5 1/2" to 4574' cemented.

No perforations Plug bottom w/ sand & 5 sacks cement

Top of cement 4520' Mud 4520' to 800'

Spotted 100 sacks cement 800' to 450' Mud 450' to 250'

Spotted 30 sacks cement 250' to 160' Mud 160' to 30'

Plug, Hulls 10 sacks cement 30' to 0'. Allied Pump Company

Pulled 1063' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9/13/68  
INV. NO. 8454-u

Signed:   
Well Plugging Supervisor