

KANSAS

15-009-15691-0000

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 18 1972
05-18-72
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name National Cooperative Refinery Association

Complete Address P. O. Box # 6, Great Bend, Kansas 67530

Lease Name Depiesse Well No. # 5

Location SE NE SE Sec. 6 Twp. 16 Rge. 12 (E) (W) W

County Barton Total Depth 3288

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Comestock Pipe Pulling, Inc.

Address 320 N. Park, Stafford, Kansas License No. # 490

Operation Completed: Hour 1:30 P.M. Day 15 Month 5 Year 1972

The above well was plugged as follows:

8 5/8" csg. 375' ~~RMK~~. No Cement. Perf. 3090'.
Sanded hole back to 3000' & dumped 5 sax cement with dump bailer. Pulled pipe.
Circulated hole with mud @ 240' & displaced 100 sax cement thru pipe A 220'.
Pulled pipe to 40' & displaced 50 sax cement thru pipe with Allied Cementing
Company's pump truck, cementing to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Don Lewis
Well Plugging Supervisor

INVOICED

DATE 5/18/72
INV. NO. 5734-W