

15-009-06510-0000

DISTRICT CONSERVATION AGENT'S REPORT

*R*

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 92-31

LOCATION SW-WF-NE

SEC. 6 TWP. 16 RGE. 12-W

Dry Hole X Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 3 Lease Staudinger - "B"

Operator Lee Phillips Oil Co. Address 407 N. Bk. Bldg. Wichita - Kans.

Field \_\_\_\_\_ County Barton

Total Depth 3308 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/8 - 448 ft. Circulated with cement  
5/8 casing set at 3300 ft. Cemented with 75 sacks cement  
Low Wells Plug at 3150 ft. Chert from 3150 ft to 3105 ft  
Mixed 5 sacks of cement at 3105 ft. Shut off & pulled  
the 5/8 casing - mud to 250 ft. Set Rock Bridge  
& 15 sacks of cement at 250 ft. - mud to 30 ft. Bridge  
& 10 sacks of cement at the surface.  
Boring Snyder - Plugging Contractor

*END*  
*07-19-51*

STATE PLUGGING DIVISION  
FILE SEC. 6-16-182  
BOOK PAGE 92 LINE 31

C. D. Stough  
District Conservation Agent

Date 7-13-51